F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94/90	*	COOK	588	32
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

62303 * (2021-922 PT2 ETC 2324.6-IP) R-11

ROADWAY ITEMS SCHEDULE

STATION		STATION	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SUB-BASE GRANULAR MATERIAL, TYPE B 24"	NOT USED	P.C.C. BASE COURSE 9-1/2"	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 14"	P.C.C. PAVEMENT 11" (JOINTED)	P.C.C. SHOULDERS 11"	SHOULDER RUMBLE STRIP	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70 (1-1/2")	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL 4.75, N50 (1")	P.C.C. SHOULDERS 14"	STABILIZED SUB-BASE 4 1/2"	PAVEMENT REINFORCEMENT, 14"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)
			SQ YD	SQ YD	SQ YD	-	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	TON	TON	SQ YD	SQ YD	SQ YD	TON	TON
3475+50.00	TO	3479+00.00	1,940	1,478	462	-	0	1,478	0	0	1,400	0	0.0	323	1,940	1,478	0.8	3.9
3479+00.00	TO	3491+00.00	8,005	6,091	1,914	-	0	6,092	0	0	4,389	0	0.0	1,425	8,005	6,092	3.3	16.1
3491+00.00	TO	3503+00.00	7,348	5,220	2,128	-	0	5,221	0	0	4,573	0	0.0	1,462	7,348	5,221	3.0	14.7
3503+00.00	TO	3515+00.00	8,825	6,169	2,656	-	0	6,169	0	0	4,307	0	0.0	1,634	8,825	6,169	3.6	17.7
3515+00.00	TO	3526+00.00	8,223	6,398	1,825	-	0	6,399	0	0	4,300	0	0.0	1,408	8,223	6,399	3.3	16.5
3526+00.00	TO	3529+00.00	2,436	1,679	1,757	-	0	1,680	0	0	1,187	0	0.0	608	2,436	1,680	1.0	4.9
3529+00.00	TO	3541+00.00	13,125	8,657	4,468	-	777	8,657	1,155	0	4,541	153.5	102.3	2,551	13,125	8,657	28.8	5.5
3541+00.00	TO	3553+00.00	10,314	6,053	4,261	-	126	6,053	1,105	134	3,987	38.7	25.8	1,602	10,314	6,053	22.2	1.4
3553+00.00	TO	3565+00.00	10,415	5,966	4,449	-	1,029	5,966	1,046	3	4,609	181.1	120.8	1,862	10,415	5,966	23.3	6.5
3565+00.00	TO	3577+00.00	10,128	6,125	4,004	-	0	6,125	820	0	3,836	0.0	0.0	2,340	10,128	6,125	21.5	0.0
3577+00.00	TO	3589+00.00	8,655	5,515	3,140	-	402	5,515	472	0	4,270	57.8	38.6	2,066	8,655	5,515	18.8	2.1
3589+00.00	TO	3601+00.00	8,627	5,207	3,420	-	0	5,207	481	0	4,569	0.0	0.0	1,997	8,627	5,207	18.3	0.0
3601+00.00	TO	3613+00.00	9,485	6,656	2,829	-	0	6,656	293	85	4,178	0.0	0.0	1,600	9,485	6,656	20.2	0.0
3613+00.00	TO	3625+00.00	9,971	6,830	3,142	-	0	6,830	267	78	4,088	0.0	0.0	2,115	9,971	6,830	21.2	0.0
3625+00.00	TO	3637+00.00	5,328	2,182	3,146	-	0	2,182	374	93	4,382	0.0	0.0	2,085	5,328	2,182	11.3	0.0
3637+00.00	TO	3638+05.00	427	0	427	-	0	0	0	0	2,039	0.0	0.0	427	427	0	1.0	0.0
		TOTAL	123,252	80,225	44,027	-	2,333	80,229	6,013	394	60,655	431.1	287.5	25,506	123,252	80,229	202	89

SCH-03

REVISIONS		
	NAME	DATE
	REVISED SHEET	6/23/06
2	ADDENDUM 2	8/04/06

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94/90 (DAN RYAN EXPRESSWAY)

GARFIELD BLVD TO 31ST STREET (SB LOCAL LANES)

ROADWAY SCHEDULES

SCALE: NTS

DATE: 06/09/06

DRAWN BY: RA

CHECKED BY: RS

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
Chicago, Illinois
312.228.0100
www.bbandainc.com

n:\660\acad\civil\9-SHEETS\660_19CSCH02.dgn

6/23/07 PM

8/7/2006