

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
599	426-15DM	ROCK ISLAND	116	15
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SCHEDULE OF QUANTITIES

TREE TRUNK PROTECTION

EACH	LOCATION	OFFSET
1	LT 1250+53	35'
1	LT 1250+83	39'
<u>2</u>	TOTAL	

EARTH EXCAVATION

CU YD	LOCATION	OFFSET
5,799	LT&RT 1240+00 - 1265+00 TURKEY HOLLOW ROAD	
<u>880</u>	LT&RT	
<u>6,679</u>	TOTAL	

SEEDING, CLASS 2A

ACRE	LOCATION	OFFSET
2.80	LT&RT 1240+00 - 1265+00	
<u>2.80</u>	TOTAL	

NITROGEN FERTILIZER NUTRIENT

POUND	LOCATION	OFFSET
252	LT&RT 1240+00 - 1265+00	
<u>252</u>	TOTAL	

PHOSPHORUS FERTILIZER NUTRIENT

POUND	LOCATION	OFFSET
252	LT&RT 1240+00 - 1265+00	
<u>252</u>	TOTAL	

POTASSIUM FERTILIZER NUTRIENT

POUND	LOCATION	OFFSET
252	LT&RT 1240+00 - 1265+00	
<u>252</u>	TOTAL	

MOWING

ACRE	LOCATION	OFFSET
2.80	LT&RT 1240+00 - 1265+00	
<u>2.80</u>	TOTAL	

MULCH, METHOD 2

ACRE	LOCATION	OFFSET
2.80	LT&RT 1240+00 - 1265+00	
<u>2.80</u>	TOTAL	

TEMPORARY EROSION CONTROL SEEDING

POUND	LOCATION	OFFSET
2,240	LT&RT 1240+00 - 1265+00	
<u>2,240</u>	TOTAL	

TEMPORARY DITCH CHECKS

EACH	LOCATION	OFFSET
1	RT 1245+50	75'
1	RT 1247+00	57'
1	RT 1250+50	56'
1	RT 1250+00	56'
1	RT 1253+21	51'
1	RT 1254+74	48'
1	LT 1255+00	30'
1	RT 1256+24	49'
1	LT 1256+50	32'
1	RT 1257+74	51'
1	LT 1258+00	31'
1	RT 1259+25	46'
1	LT 1259+50	32'
1	RT 1260+50	46'
1	LT 1261+00	32'
1	RT 1262+00	47'
1	LT 1262+50	32'
1	RT 1263+73	48'
1	LT 1264+00	35'
TURKEY HOLLOW ROAD		
1	LT 99+00	38'
1	RT 99+00	35'
<u>21</u>	TOTAL	

PERIMETER EROSION BARRIER

FOOT	LOCATION	OFFSET
1,155	RT 1240+00	- 1250+93
1,168	LT 1240+52	- 1251+28
1,307	RT 1252+08	- 1264+61
1,301	LT 1251+48	- 1264+44
46	LT 1264+63	- 1265+00
TURKEY HOLLOW ROAD		
298	RT 97+00	- 99+25
286	LT 97+00	- 99+27
<u>5,561</u>	TOTAL	

INLET AND PIPE PROTECTION

EACH	LOCATION	OFFSET
1	RT 1245+48	47'
1	RT 1258+00	52'
1	RT 1261+00	55'
1	RT 1262+50	55'
1	RT 1264+00	52'
1	RT 1264+04	98'
1	RT 1264+45	51'
1	LT 1264+31	33'
<u>8</u>	TOTAL	

STONE RIPRAP, CLASS A4

SQ YD	LOCATION	OFFSET
32	LT 1245+44	59' (15' X 19')
<u>32</u>	TOTAL	

FILTER FABRIC

SQ YD	LOCATION	OFFSET
32	LT 1245+44	59' (15' X 19')
<u>32</u>	TOTAL	

PLOT DATE = Wed Jun 21 13:08:19 2006
FILE NAME = c:\p\proj\mets\207784\80784.dwg
PLOT SCALE = 50.0000 / IN
USER NAME = mg11j

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE:	VERT. DATE	HORIZ. DRAWN BY CHECKED BY

SCHEDULE OF QUANTITIES