

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
599	026-15D/M	ROCK ISLAND	116	16
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID	PROJECT	

SCHEDULE OF QUANTITIES

SUB-BASE GRANULAR MATERIAL TYPE A 12"

SQ YD	LOCATION			
640	RT	1240+84	-	1245+50
2,350	RT	1255+50	-	1264+51
6	LT&RT	1242+00		
6	LT&RT	1244+50		(FOR AGG BASE DRAIN)
3	LT	1256+25		(FOR AGG BASE DRAIN)
3	LT	1258+25		(FOR AGG BASE DRAIN)
3	LT	1260+25		(FOR AGG BASE DRAIN)
3	LT	1262+25		(FOR AGG BASE DRAIN)
3	LT	1264+00		(FOR AGG BASE DRAIN)
<u>3,017</u>	TOTAL			

SUB-BASE GRANULAR MATERIAL TYPE A 15"

SQ YD	LOCATION			
813	RT	1245+50	-	1248+50
6	LT&RT	1247+00		(FOR AGG BASE DRAIN)
217	RT	1254+50	-	1255+50
<u>1036</u>	TOTAL			

SUB-BASE GRANULAR MATERIAL TYPE A 24"

SQ YD	LOCATION			
1804	RT	1248+50	-	1254+50
6	LT&RT	1249+50		(FOR AGG BASE DRAIN)
3	LT	1252+19		(FOR AGG BASE DRAIN)
3	LT	1254+25		(FOR AGG BASE DRAIN)
	TURKEY HOLLOW ROAD			
818	RT<	97+50	-	99+59
3	RT<	99+11		(FOR AGG BASE DRAIN)
<u>2637</u>	TOTAL			

AGGREGATE BASE COURSE TYPE B

TON	LOCATION			
90	RT	1237+21	-	1238+21
572	RT	1238+21	-	1246+04
89	LT	1237+21	-	1238+22
2856	LT	1238+21	-	1264+51
217	LT	1264+51	-	1267+54
<u>3824</u>	TOTAL			

AGGREGATE SURFACE COURSE TYPE B

TON	LOCATION				
12	LT	1240+26		PE	(TEMPORARY ACCESS)
7	LT	1251+39		PE	(TEMPORARY ACCESS)
8	LT	1264+55		PE	(TEMPORARY ACCESS)
<u>27</u>	TOTAL				

BITUMINOUS MATERIALS (PRIME COAT)

TON	LOCATION				
1.1	LT	1237+23	-	1269+03	(NORTH SHOULDER)
3.6	RT & LT	1240+00	-	1264+51	(SURFACE COURSE)
1.8	RT & LT	1240+00	-	1264+51	(4-1/2" MILLED AREA)
0.5	3 PE'S				(ENTRANCES)
<u>7</u>	TOTAL				

AGGREGATE (PRIME COAT)

TON	LOCATION			
18	RT & LT	1240+00	-	1264+51
18	TOTAL			

TEMPORARY RAMP

SQ YD	LOCATION			
130	RT & LT	1240+00		
260	RT & LT	1264+51		
	TURKEY HOLLOW ROAD			
130	RT & LT	97+50		
<u>520</u>	TOTAL			

INCIDENTAL BITUMINOUS SURFACING

TON	LOCATION			
11	LT	1240+26		PE
7	LT	1251+39		PE
8	LT	1264+55		PE
<u>26</u>				

BITUMINOUS SURFACE REMOVAL 4 1/2"

SQ YD	LOCATION			
6030	RT & LT	1240+00	-	1264+51
6030	TOTAL			

PAVEMENT REMOVAL

SQ YD	LOCATION			
1972	RT	1240+84	-	1264+51
	TURKEY HOLLOW ROAD			
586	RT & LT	97+50	-	99+61
<u>2558</u>	TOTAL			

COMBINATION CURB AND GUTTER REMOVAL

FOOT	LOCATION				
45	RT	1251+75			(MEDIAN)
5	RT	1264+46	-	1264+51	
<u>50</u>	TOTAL				

CONCRETE MEDIAN SURFACE REMOVAL

SQ FT	LOCATION			
119	RT	1251+75		
<u>119</u>	TOTAL			

PAVEMENT PATCHING TYPE I

SQ YD	LOCATION			
45		TO BE DETERMINED BY ENGINEER		
<u>45</u>	TOTAL			

PLOT DATE = Wed Jun 21 13:05:20 2006
 FILE NAME = c:\p\c\mets\p237076\1\08176rev.dgn
 PLOT SCALE = 50.0000 : 1 IN.
 USER NAME = mgilju

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY

SCHEDULE OF QUANTITIES