CONTRACT NO. 64C67

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	***	17	2
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*=FAP 646 & FAP 638
**=101BY-D & 137-1B-D
***=WHITESIDE & HENRY

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	SFTY-2A IL 40 WHITESIDE SN: 098-0015 100 % STATE	SFTY-2A US 30 HENRY SN: 037- 0106 100 % STATE
44001000	BITUMINOUS CONCRETE SURFACE REMOVAL	SQ YD	23.5	18.5	5
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ. FT.	650	650	
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ. FT.	252		252
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	210	210	
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	125.7	91.7	34
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	459	330	129
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100325	TRAFFIC CONTROL AND PROTECTION STD 701423	EACH	1	1	
70103815	TRAFFIC CONTROL SURVEILANCE	CAL DA	3	2	1
70300200	TEMPORARY PAVEMENT MARKING	FOOT	2760	2760	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	919	919	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	120	120	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	120	120	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4880	4600	280
78300105	PAVEMENT MARKING REMOVAL	FOOT	920	920	
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SQ FT	915	659	256
X0322932	SILICONE JOINT SEALER, 1 1/2"	FOOT	25	25	
X4066424	BITUMINOUS CONCRETE SURFACE COARSE, SUPERPAVE, MIX "D", N50	TON	18.8	10.3	8.5
X0712400	TEMPORARY PAVEMENT	SQ YD	100	72	28
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	100	72	28
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1		1
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	4	4	
⊙ Z0030250	IMPACT ATTENUATOR, TEMPRARY(NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
⊙ Z0030350	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	

* SPECIALTY ITEMS
⊙ SFTY-3N

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = Mon Jul 10 11:15:19 2006
FILE NAME = s:\proj=sys\c211606\sht1686sum.dgn
PLOT SCALE = 20.0000 ' / IN.
USER NAME = goffjl