

# GENERAL NOTES

ROUTE NO.	SEC.	COUNTY	TOTAL SHEETS	SHEET NO.
FAP 646 (IL 40) & FAP 638 (IL 82)	101BY-D & 137-1B-D	Whiteside & Henry	17	3
FED ROAD DIST. NO.	ILLINOIS	PROJECT		
Contract #64C67				

Any disturbed area caused by construction shall be seeded using Class 2A by the Contractor at his expense with no cost to the Department.

The following Mixture Requirements are applicable for this project:

	IL 40	IL 82
Mixture Uses(s):	Mainline Surface Course	Mainline Surface Course
PG:	PG 64-22	PG 64-22
RAP%: (Max)	15%	15%
Design Air Voids	4.2 @ N50	4.2 @ N50
Mixture Composition (Gradation Mixture)	IL 9.5 or 12.5	IL 9.5 or 12.5
Friction Aggregate	D	C
20 Year ESAL	2.3	0.7

Bituminous prime coat shall be placed in accordance with Section 406 of the Standard Specifications. The cost of the prime coats shall be included in the contract unit price per ton for BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE Mix "D", N50.

These structures will retain the same numbers SN 098-0015 & 037-0106.

Pavement Marking shall be done according to Standard 780001, except as follows:

1. All words, such as ONLY, shall be 2.4 m (8 feet) high.
2. All non-freeway arrows shall be the large size.
3. The distance between yellow no-passing lines shall be 200 mm (8"), not 180 mm (7") as shown in the detail of Typical Lane and Edge Lines.

All work on the structures over the Hennepin Feeder Canal & the north branch of Spring Creek, shall be performed from the existing deck and that no work shall take place below the existing structure on the ground.

No vehicles or materials shall be parked or stored outside the state right-of-way

No vehicles or materials shall be parked or stored on the Hennepin Feeder Canal property, which is owned by the Illinois Department of Natural Resources

The bike path located on the west towpath of the Hennepin Feeder Canal shall not be closed for any duration to exceed one hour.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

Commonwealth Edison Co.  
AT&T  
NICOR Gas Co.  
Insight Communications of Rockford  
Lightcore

Cambridge Telephone  
Corn Belt Energy Corp.  
City of Rock Falls  
Norlight Telecommunications  
Aldridge Electric

Program #5  
(Arch. Size)  
Enlarge  
200%  
Enlarge 107%