

FAS	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1379	(108-B-1) BR	STARK	43	4
STA. 46+00		TO STA. 63+50		
FED. ROAD DIST. NO.		ILLINOIS	IL 91	

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

80% FED
20% STATE

80% FED
20% STATE

CODE NO.	ITEM	UNIT	80% FED 20% STATE			CODE NO.	ITEM	UNIT	80% FED 20% STATE		
			PROPOSED SN 088-2004 X028-2A	1000	TOTAL				PROPOSED SN 088-2004 X028-2A	1000	TOTAL
20100210	TREE REMOVAL, (OVER 15 UNITS DIAMETER)	UNIT	0	35	35	28200200	FILTER FABRIC	SQ YD	0	697	697
20100500	TREE REMOVAL, ACRES	ACRE	0.0	0.1	0.1	31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	0	807	807
20200100	EARTH EXCAVATION	CU YD	0	2808	2808	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0	2.2	2.2
20200500	EARTH EXCAVATION WIDENING	CU YD	0	296	296	40600300	AGGREGATE (PRIME COAT)	TON	0	11	11
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	204	98	302	40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	0	174	174
20400800	FURNISHED EXCAVATION	CU YD	0	1706	1706	40600990	TEMPORARY RAMP	SQ YD	0	40	40
20800150	TRENCH BACKFILL	CU YD	0	22	22	44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	0	3380	3380
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	377	211	588	44000100	PAVEMENT REMOVAL	SQ YD	0	996	996
21101615	TOPSOIL FURNISH & PLACE, 4"	SQ YD	0	12177	12177	48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	0	1167	1167
25000300	SEEDING, CLASS 3	ACRE	0.0	2.4	2.4	50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	0	1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	0	216	216	50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	0	1	1
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	0	216	216	50105200	REMOVE EXISTING CULVERTS	EACH	0	1	1
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	0	216	216	51500100	NAME PLATES	EACH	1	0	1
25100115	MULCH, METHOD 2	ACRE	0	2.4	2.4	54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	2	0	2
25100630	EROSION CONTROL BLANKET	SQ YD	0.0	1967	1967	54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	0	2	2
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	0	720	720	54011006	PRECAST CONCRETE BOX CULVERT 10' x 6'	FOOT	0	84	84
28000300	TEMPORARY DITCH CHECKS	EACH	0	15	15	54011009	PRECAST CONCRETE BOX CULVERT 10' X 9'	FOOT	192	0	192
28000400	PERIMETER EROSION BARRIER	FOOT	0	1228	1228	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTION 18"	EACH	0	2	2
28000500	INLET AND PIPE PROTECTION	EACH	0	1	1	542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	0	74	74
28100207	STONE RIPRAP, CLASS A4	TON	0	318	318	542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	0	175	175
28100209	STONE RIPRAP, CLASS A5	TON	0	202	202	63200310	GUARDRAIL REMOVAL	FOOT	0	1967	1967