

FAS	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1379	(108-B-1) BR	STARK	43	5
STA. 46+00		TO STA. 63+50		
FED. ROAD DIST. NO.		ILLINOIS		IL 91

**ILLINOIS DEPARTMENT OF TRANSPORTATION**  
**SUMMARY OF QUANTITIES**

80% FED.  
20% STATE

CODE NO.	ITEM	UNIT	PROPOSED SN 088-2004 X028-2A	1000	TOTAL
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	0	21	21
66700205	PERMANENT SURVEY MARKERS TYPE I	EACH	0	3	3
66700605	PERMANENT SURVEY TIES	EACH	0	4	4
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	0	6	6
67100100	MOBILIZATION	L SUM	0	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	0	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	0	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	0	1	1
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	0	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	0	175	175
70300200	TEMPORARY PAVEMENT MARKING	FOOT	0	3938	3938
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	0	58	58
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	0	3938	3938
X0320678	TREE WHIP MIXTURE	EACH	0	2	2
X3560140	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 10 INCH	SQ YD	0	1400	1400
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	0	603	603
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	0	475	475
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	0	129	129
Z0013798	CONSTRUCTION LAYOUT	L SUM	0	1	1
Z0023600	FILLING EXISTING CULVERTS	EACH	0	1	1
Z0054500	ROCK FILL	TON	409	204	613

\*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**

SCALE: NO SCALE  
DATE: 06-02-03

DRAWN BY: BAD  
CHECKED BY: JLG