

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
516	241BR & 56BR	CHAMPAIGN	82	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES
SHEET 1 OF 3

11.5 5

BHS **RS**

FAS 516 / CH 12
SECTION 241BR
RURAL
STA. 1+12.00
TO
STA. 6+00.00
S. N. 010-0221
80% FED
20% STATE
X080-2A

FAS 516 / CH 12
SECTION 56BR
RURAL
STA. 135+50.00
TO
STA. 140+00.00
S. N. 010-2028
80% FED
20% STATE
X028-2A

LOCATION OF WORK:

FUNDING BREAKOUT:

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY
20200100	EARTH EXCAVATION	CU YD	810.0	5.0	805.0
20300100	CHANNEL EXCAVATION	CU YD	849.0		849.0
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	34.0	34.0	
20900110	POROUS GRANULAR BACKFILL	CU YD	308.0		308.0
25000200	SEEDING, CLASS 2	ACRE	0.9	0.4	0.5
25000350	SEEDING, CLASS 7	ACRE	0.9	0.4	0.5
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	77.0	31.0	46.0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	77.0	31.0	46.0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	77.0	31.0	46.0
25100115	MULCH, METHOD 2	ACRE	0.9	0.4	0.5
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	85.0	34.0	51.0
28000300	TEMPORARY DITCH CHECKS	EACH	7.0		7.0
28000400	PERIMETER EROSION BARRIER	FOOT	1,242.0	928.0	314.0
28000500	INLET AND PIPE PROTECTION	EACH	2.0	1.0	1.0
28100107	STONE RIPRAP, CLASS A-4	SQ YD	931.0	606.0	325.0
28200200	FILTER FABRIC	SQ YD	931.0	606.0	325.0
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	81.0	59.0	22.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	238.0	118.0	120.0
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	615.0	348.0	267.0
• SPECIALTY ITEM					

PLOT DATE = 6/30/2006
FILE NAME = c:\projects\70359\70359.dwg
PLOT SCALE = 1/8" = 1'-0"
USER NAME = p1er-sonb

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
(SHEET 1 OF 3)
F.A.S. 516/(C.H. 12)
SECTION 241BR & 56BR
CHAMPAIGN COUNTY

SCALE: NOT TO SCALE DRAWN BY: B.B.P.
DATE: 05/12/06 CHECKED BY: G.A.E.