

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
516	241BR & 56BR	CHAMPAIGN	82	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

SHEET 3 OF 3

BHS RS

LOCATION OF WORK:

FAS 516 / CH 12
SECTION 241BR
RURAL
STA. 1+12.00
TO
STA. 6+00.00
S. N. 010-0221
80% FED
20% STATE
X080-2A

FAS 516 / CH 12
SECTION 56BR
RURAL
STA. 135+50.00
TO
STA. 140+00.00
S. N. 010-2028
80% FED
20% STATE
X028-2A

FUNDING BREAKOUT:

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY
• 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	475.0	150.0	325.0
• 63000005	STEEL PLATE BEAM GUARDRAIL, TYPE B	FOOT	100.0		100.0
• 63000025	STEEL PLATE BEAM GUARDRAIL ATTACHED TO STRUCTURE	FOOT	50.0		50.0
• 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4.0	3.0	1.0
• 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4.0	4.0	
• 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	6.0	3.0	3.0
63200310	GUARDRAIL REMOVAL	FOOT	475.0	225.0	250.0
• 63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	54.0	40.5	13.5
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	8.0		8.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5.0	2.0	3.0
67100100	MOBILIZATION	L SUM	1.0	0.5	0.5
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1.0	0.5	0.5
• 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2,126.0	1,106.0	1,020.0
• 78200405	GUARDRAIL MARKERS	EACH	20.0	12.0	8.0
• 78201000	TERMINAL MARKER DIRECT APPLIED	EACH	10.0	6.0	4.0
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5")	SO FT	2.0	2.0	
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	209.0	104.0	105.0
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	232.0		232.0
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE, N50	TON	70.0	70.0	
X5030305	CONCRETE WEARING SURFACE, 5"	SO YD	400.0	400.0	
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1.0	0.5	0.5
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	22.0	22.0	
Z0038700	PERMANENT BENCH MARKS	EACH	2.0	1.0	1.0
•	SPECIALTY ITEM				

PLOT DATE : 6/30/2006
 FILE NAME : c:\projects\fd501304 (v8)\comment.txt.dgn
 PLOT SCALE : 43.2355' / IN.
 USER NAME : piersonb

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
(SHEET 3 OF 3)

F.A.S. 516/(C.H. 12)
SECTION 241BR & 56BR
CHAMPAIGN COUNTY

SCALE: NOT TO SCALE DRAWN BY: B.B.P.
DATE: 05/12/06 CHECKED BY: G.A.E.