



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

August 28, 2006

SUBJECT: FAI Route 64 (I-64)  
Section 95-5HB-RS  
Washington County  
Contract No. 76A12  
Item No. 15, September 22, 2006 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 2 of the Schedule of Prices.
2. Revised sheets 2 and 5 of the Plans.
3. Revised page 9 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine  
Engineer of Design  
and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger' followed by a small 'P.E.' to the right.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Mary C. Lamie, Region 5, District 8; Roger Driskell; R. E. Anderson;  
Estimates; Design & Environment File

TBW:DB:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 76A12

State Job # - C-98-039-06  
 PPS NBR - 0-00857-8016  
 County Name - WASHINGTON- -  
 Code - 189 - -  
 District - 8 - -  
 Section Number - 95-5HB-RS

Project Number

Route  
 FAI 64

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50300530	FLOOR DRAIN EXTENSION	EACH	4.000				
67000400	ENGR FIELD OFFICE A	CAL MO	6.000				
67100100	MOBILIZATION	L SUM	1.000				
70100100	TRAF CONT-PROT 701316	EACH	1.000				
* 70100700	TRAF CONT-PROT 701406	L SUM	1.000				
70106600	TEMP BR TRAF SIG SFC	EACH	1.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	96.000				
78001110	PAINT PVT MK LINE 4	FOOT	148.000				
* REVISED : AUGUST 28, 2006							


TOTAL SHEETS	SHEET NO.
17	2
CONTRACT NO.: 76A12	

INDEX OF SHEETS

1. COVER SHEET
2. INDEX OF SHEETS AND HIGHWAY STANDARDS
- 3-4. GENERAL NOTES
- 5-6. SUMMARY OF QUANTITIES
7. LOCATION MAP
8. ROADWAY TYPICAL SECTION AND MILLING DETAIL
9. BRIDGE PLAN
10. BRIDGE ELEVATION
11. BRIDGE CROSS SECTION
12. PATCHING SCHEDULE
13. BRIDGE DECK PATCHING SURVEY
14. SILICONE JOINT SEALER AND POLYMER CONCRETE DETAILS
15. DRAIN EXTENSION DETAILS
16. ALTERNATE DRAIN EXTENSION DETAILS
17. DRAIN PLUG DETAIL

HIGHWAY STANDARDS


- 000001-04
- 701006-02
- 701011-01
- 701311-02
- 701316-03
- 702001-06
- 780001-01

701406-04 

INDEX OF SHEETS AND  
HIGHWAY STANDARDS

FAI 64 (I-64)  
SECTION 95-5HB-RS  
WASHINGTON COUNTY

\$\$\$DATE\$\$  
\*DATE-TIME\*  
\*DCN-SPEC\*

 Rev. 8-27-06

PLOT DATE: \*DATE-TIME\*

# SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	SFTY-2A	CONSTRUCTION TYPE CODE	
40600990	TEMPORARY RAMP	SQ YD	35	35		
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.2	0.2		
40800030	AGGREGATE (PRIME COAT)	TON	1	1		
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	36	36		
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	289	289		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2	2		
50300260	BRIDGE DECK GROOVING	SQ YD	738	738		
50300300	PROTECTIVE COAT	SQ YD	738	738		
50300530	FLOOR DRAIN EXTENSION	EACH	4	4		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1	1		
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1		△

**SUMMARY OF QUANTITIES**  
 FAI 64 (I-64)  
 SECTION 95-5HB-RS  
 WASHINGTON COUNTY  
 PLOT DATE: \*DATE-TIME\*

\*\*DATES\*\*  
 \*DATE-TIME\*  
 \*DGN-SPEC\*

△ Rev. 8-27-06

701006      701011      701311      701316      701406      702001

In addition, the following Special Provision(s) will also govern traffic control for this project:

Construction and Maintenance Sign Supports  
Flagger Vests  
Personal Protective Equipment  
Temporary Portable Bridge Traffic Signals  
Traffic Control Deficiency Deduction  
Work Zone Traffic Control Devices

### **CONSTRUCTION AND MAINTENANCE SIGN SUPPORTS**

*Effective: April 21, 1981*

*Revised: October 15, 1996*

This work shall be done in accordance with Article 1084.04 of the Standard Specifications and Highway Standard 702001 except as herein modified.

All construction signs mounted on permanent support for use in temporary traffic control having an area of 1 square meter (10 square feet) or more shall be mounted on two 100 mm x 100 mm (4 in x 4 in) or two 100 mm x 150 mm (4 in x 6 in) wood posts.

Type A metal post (two for each sign) conforming to Article 1006.29 of the Standard Specifications may be used in lieu of wood posts. Type A metal posts used for these signs may be unfinished.

This work shall not be measured and paid for but shall be considered incidental to the contract.

Revised 08/28/2006