

SCHEDULE OF QUANTITIES

Item No.	Description	Quantity	Unit
25000500	PHOSPHOROUS FERTILIZER NUTRIENT		POUND
	85TH AVENUE WEST		
	CLASS 1 SEEDING AREAS	243	
	CLASS 3 SEEDING AREAS	63	
	SODDED AREAS	102	
	OLD 85TH AVENUE WEST		
	CLASS 1 SEEDING AREA	27	
	TURKEY HOLLOW ROAD		
	CLASS 1 SEEDING AREA	13	
	51ST STREET		
	CLASS 1 SEEDING AREAS	74	
	42ND AVENUE		
	SODDED AREAS	1	
	TOTAL	523	
25000600	POTASSIUM FERTILIZER NUTRIENT		POUND
	85TH AVENUE WEST		
	CLASS 1 SEEDING AREAS	243	
	CLASS 3 SEEDING AREAS	63	
	SODDED AREAS	102	
	OLD 85TH AVENUE WEST		
	CLASS 1 SEEDING AREA	27	
	TURKEY HOLLOW ROAD		
	CLASS 1 SEEDING AREA	13	
	51ST STREET		
	CLASS 1 SEEDING AREAS	74	
	42ND AVENUE		
	SODDED AREAS	1	
	TOTAL	523	
25000910	SEEDING, CLASS 1 (MODIFIED)		ACRE
	85TH AVENUE WEST		
	LT. & RT. STA. 10+50-25+00	1.35	
	RT. STA. 31+82-32+35	0.03	
	LT. STA. 26+50-39+20	0.64	
	LT. STA. 44+73-47+50	0.13	
	LT. STA. 51+10-52+25	0.05	
	RT. STA. 52+50-56+00	0.11	
	LT. STA. 65+05-76+00	0.38	
	OLD 85TH AVENUE WEST		
	LT. & RT. STA. 0+25-3+00	0.3	
	TURKEY HOLLOW ROAD		
	RT. STA. 200+00-205+00 (TURN LANE)	0.14	
	51ST STREET		
	LT. & RT. STA. 99+50	0.82	
	TOTAL	4.0	
25100115	MULCH, METHOD 2		ACRE
	ALL SEEDING CLASS 1 AREAS	4	
	ALL TEMPORARY EROSION CONTROL SEEDING AREAS	4.7	
	TOTAL	8.7	

Item No.	Description	Quantity	Unit
25100125	MULCH, METHOD 3		ACRE
	SEEDING CLASS 3 AREAS	0.7	
	TOTAL	0.7	
25100630	EROSION CONTROL BLANKET		S.Y.
	85TH AVENUE WEST		
	RT. STA. 25+75-28+40 (1:2 SLOPE)	368	
	RT. STA. 28+60-31+70 (1:2 SLOPE)	436	
	LT. STA. 47+25-48+00 (1:2 SLOPE)	100	
	RT. STA. 56+00-64+00 (1:2 SLOPE)	1,547	
	RT. STA. 66+50-67+50 (1:2 SLOPE)	192	
	LT. STA. 10+84 (RCP OUTLET)	2	
	RT. STA. 26+00 (RCP OUTLET)	2	
	LT. STA. 30+80 (RCP OUTLET)	2	
	LT. STA. 72+00 (RCP OUTLET)	2	
	TOTAL	2,651	
25200100	SODDING		S.Y.
	85TH AVENUE WEST		
	RT. STA. 32+35-47+71	3,295	
	LT. STA. 39+15-44+76	1,154	
	LT. STA. 48+10-51+10	675	
	RT. STA. 48+31-52+50	1,275	
	LT. STA. 52+22-65+21	836	
	RT. STA. 64+50-75+50	951	
	42ND AVENUE		
	LT. & RT. STA. 2+50-3+05	99	
	TOTAL	8,285	
25200200	SUPPLEMENTAL WATERING		UNIT
	ALL SODDED AREAS (3 APPLICATIONS)	75	
	TOTAL	75	
25301200	SALVAGING AND TRANSPLANTING TREES, SPECIAL		EACH
	85TH AVENUE WEST		
	RT. STA. 49+65 - 52+55	90	
	TOTAL	90	
28000250	TEMPORARY EROSION CONTROL SEEDING		POUND
	AREAS TO BE CLASS 1 OR 3 SEEDED (4 APPLICATIONS ASSUMED)	1,880	
	TOTAL	1,880	
28000300	TEMPORARY DITCH CHECKS		EACH
	85TH AVENUE WEST		
	RT. STA. 11+00	1	
	LT. STA. 11+95	1	
	LT. STA. 12+90	1	

REVISIONS	DESCRIPTION	DATE
No.		



Missman
STANLEY & ASSOCIATES, P.C.
Civil Engineering-Environmental Services-GIS-Landscape Architecture-Surveying
1011 27th Avenue
Rock Island, Illinois 61201-6040
Phone (309) 788-7644 Fax (309) 788-7691

85th Ave. West
ROCK ISLAND, ILLINOIS

SCHEDULE OF QUANTITIES

Missman Project No:
A04T023

File Name:
2037A_SUM&SCH.dwg

© COPYRIGHT 2003
ALL RIGHTS RESERVED

Drawn By: WEF

Checked By: DRM

Date: MAY, 2006

13

Sheet 13 of 94

G:\R\2004\A04T023-85AVF WEST.dwg 2037A_SUM&SCH.dwg 6/6/2006 8:46:52 AM