

SCHEDULE OF QUANTITIES

	51ST STREET	
	LT. & RT. STA. 100+00-100+85.5	392
	LT. & RT. STA. 101+09.7-104+89.3	1,701
	41ST STREET	
	LT. STA. 61+03.5-62+41.9	543
	TOTAL	20,197
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	S.Y.
	85TH AVENUE WEST	
	RT. STA. 15+54	44
	RT. STA. 17+98	88
	LT. STA. 18+50	81
	RT. STA. 19+04	46
	RT. STA. 19+58	45
	RT. STA. 28+48	51
	RT. STA. 33+85	53
	RT. STA. 34+56	41
	RT. STA. 36+41	38
	RT. STA. 38+37	56
	LT. STA. 40+53	62
	RT. STA. 41+53	57
	LT. STA. 41+93	84
	LT. STA. 43+94	77
	RT. STA. 44+02	60
	LT. STA. 44+92	82
	RT. STA. 45+97	50
	RT. STA. 46+20	49
	RT. STA. 49+48	66
	LT. STA. 49+85	61
	RT. STA. 52+83	143
	LT. STA. 53+13	116
	LT. STA. 57+11	98
	RT. STA. 64+16	124
	LT. STA. 64+57	154
	LT. STA. 65+20	105
	RT. STA. 65+65	90
	RT. STA. 68+38	81
	RT. STA. 69+75	62
	RT. STA. 73+16	66
	RT. STA. 74+73	61
	TOTAL	2,291
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT
	NW RETURN 42ND STREET	94
	NE RETURN 42ND STREET	98
	TOTAL	192
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FT.
	85TH AVENUE WEST	
	RT. STA. 24+93-25+92	80
	TOTAL	80

542A0229	PIPE CULVERTS, CLASS A TYPE 1 24"	FT.
	85TH AVENUE WEST	
	LT. & RT. STA. 10+82	52
	LT. & RT. STA. 26+20	79
	TOTAL	131
542A0235	PIPE CULVERTS, CLASS A, TYPE 1 30"	FT.
	85TH AVENUE WEST	
	LT. & RT. STA. 30+84	69
	TOTAL	69
542A5485	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND - SIZE 30"	FT.
	85TH AVENUE WEST	
	LT. & RT. STA. 20+38	60
	RT. STA. 33+53-34+15	50
	TOTAL	110
542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT
	85TH AVENUE WEST	
	RT. STA. 15+36-15+75	36
	RT. STA. 18+89-19+18	29
	RT. STA. 38+13-38+62	46
	LT. STA. 40+41-40+70	26
	LT. STA. 49+67-50+00	30
	LT. STA. 41+78-42+08	26
	TOTAL	193
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT
	85TH AVENUE WEST	
	RT. STA. 17+83-18+13	42
	RT. STA. 41+35-41+71	33
	LT. STA. 43+80-44+12	28
	LT. STA. 44+79-45+05	23
	TOTAL	126
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT
	85TH AVENUE WEST	
	RT. STA. 28+35-28+60	19
	RT. STA. 34+40-34+75	33
	RT. STA. 43+85-44+26	37
	RT. STA. 49+33-49+63	25
	TOTAL	114

REVISIONS	DESCRIPTION	DATE
No.		



Missman
STANLEY & ASSOCIATES, P.C.

Civil Engineering-Environmental Services-GIS-Landscape Architecture-Surveying
Rock Island, Illinois 61201-6040
Phone (309) 786-7644 Fax (309) 786-7661

85th Ave. West
ROCK ISLAND, ILLINOIS

SCHEDULE OF QUANTITIES

Missman Project No:
A04T023

File Name:
2037A_SUM&SCH.dwg

© COPYRIGHT 2003
ALL RIGHTS RESERVED

Drawn By: WEF

Checked By: DRM

Date: MAY, 2006

G:\R\2004\A04T023-85AVE WEST.dwg 2037A_SUM&SCH.dwg 6/6/2006 8:47:07 AM