

# SCHEDULE OF QUANTITIES

	RT. STA. 202+67 (RT. TURN ARROW)	15.6
	RT. STA. 203+67 (RT. TURN ARROW)	15.6
	RT. STA. 204+67 (RT. TURN ARROW)	15.6
	TOTAL	46.8
7800110	PAINT PAVEMENT MARKING, TYPE B-LINE 4"	FOOT
	SKIP-DASHED WHITE	
	85TH AVENUE WEST	
	CL STA. 10+65-26+62 (10' DASH-30'SKIP)	400
	CL STA. 35+59-61+20 (10' DASH-30'SKIP)	640
	CL STA. 62+20-69+34 (10' DASH-30'SKIP)	180
	SUB-TOTAL	1,220
	SOLID YELLOW ("NO PASSING")	
	85TH AVENUE WEST	
	RT. STA. 12+34-21+62	928
	LT. STA. 25+91-26+62	71
	LT. & RT. STA. 26+62-35+59	1,794
	LT. STA. 35+59-49+13	1,354
	RT. STA. 55+82-61+20	538
	RT. STA. 62+20-69+34	714
	LT. & RT. STA. 69+34-76+50	1,432
	SUB-TOTAL	6,831
	SOLID WHITE	
	85TH AVENUE WEST	
	RT. STA. 11+10-25+31 (EDGE LINE)	1,464
	LT. STA. 11+08-25+34.21 (EDGE LINE)	1,446
	RT. STA. 25+54-75+46 (EDGE LINE)	5,021
	LT. STA. 25+74-61+61.6 (EDGE LINE)	3,922
	LT. STA. 61+94-75+45 (EDGE LINE)	1,397
	TURKEY HOLLOW ROAD	
	RT. STA. 200+06-205+45 (EDGE LINE)	568
	RT. STA. 206+10-205+67 (EDGE LINE)	83
	SUB-TOTAL	13,901
	TOTAL	21,952
78001140	PAINT PAVEMENT MARKING, TYPE B-LINE 8"	FOOT
	SOLID WHITE	
	TURKEY HOLLOW ROAD	
	RT. STA. 202+47-204+87 (RT. TURN LANE)	240
	SKIP-DASHED WHITE (2' DASH, 6' SKIP)	
	RT. STA. 200+05-202+47 (RT. TURN LANE)	60
	TOTAL	300
78001180	PAINT PAVEMENT MARKING, TYPE B-LINE 24"	FOOT
	SOLID WHITE STOP BARS	
	85TH AVENUE WEST	
	LT. STA. 10+65	29

	LT. STA. 25+04-25+47	43
	RT. STA. 25+47-25+75	28
	LT. STA. 61+40-61+57	26
	TOTAL	126
78200410	GUARDRAIL MARKERS, TYPE A	EACH
	85TH AVENUE WEST	
	LT. STA. 47+16	1
	LT. STA. 47+66	1
	LT. STA. 48+16	1
	LT. STA. 48+66	1
	RT. STA. 47+46	1
	RT. STA. 48+03	1
	RT. STA. 48+59	1
	RT. STA. 49+16	1
	TOTAL	8
X0322936	REMOVE EXISTING FLARED END SECTION	EACH
	85TH AVENUE WEST	
	RT. STA. 64+62	1
	TOTAL	1
X0488100	REMOVING EXISTING SEPTIC TANK	EACH
	85TH AVENUE WEST	
	47'-52' RT. STA. 42+90	2
	TOTAL	2
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON
	85TH AVENUE WEST	
	LT. STA. 10+50-25+20	176
	RT. STA. 10+86-25+36	171
	RT. STA. 25+58-47+68	241
	LT. STA. 25+76-47+60	252
	LT. STA. 48+21-75+51	303
	RT. STA. 48+30-75+58	316
	TOTAL	1,459
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON
	85TH AVENUE WEST	
	LT. STA. 10+50-25+20	264
	RT. STA. 10+86-25+36	255
	RT. STA. 25+58-47+68	362
	LT. STA. 25+76-47+60	379
	LT. STA. 48+21-75+51	453
	RT. STA. 48+30-75+58	475
	TOTAL	2,188

REVISIONS		DATE
No.	DESCRIPTION	



**Missman**  
STANLEY & ASSOCIATES, P.C.

Civil Engineering • Environmental Services • GIS • Landscape Architecture • Surveying  
1011 27th Avenue  
Rock Island, Illinois 61201-6040  
Phone (309) 786-7644 Fax (309) 786-7681

85th Ave. West  
ROCK ISLAND, ILLINOIS

## SCHEDULE OF QUANTITIES

Missman Project No:  
A04T023

File Name:  
2037A\_SUM&SCH.dwg

© COPYRIGHT 2003  
ALL RIGHTS RESERVED

Drawn By: WEF

Checked By: DRM

Date: MAY, 2006

G:\P\2004\A04T023-85AVE WFS\1.dwg 2037A\_SUM&SCH.dwg 6/6/2006 8:47:40 AM