

# SCHEDULE OF QUANTITIES

A2000118	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 3" CALIPER, BALLED AND BURLAPPED	EACH
	85TH AVENUE WEST	
	145' LT. STA. 11+90	1
	105' LT. STA. 12+34	1
	145' LT. STA. 12+72	1
	36' LT. STA. 13+00	1
	36' LT. STA. 15+00	1
	36' LT. STA. 17+00	1
	36' LT. STA. 19+00	1
	52' LT. STA. 21+00	1
	65' LT. STA. 23+00	1
	49' LT. STA. 28+00	1
	49' LT. STA. 30+00	1
	49' LT. STA. 32+00	1
	49' LT. STA. 34+00	1
	49' LT. STA. 36+00	1
	49' LT. STA. 38+00	1
	43' LT. STA. 68+00	1
	43' LT. STA. 70+00	1
	43' LT. STA. 73+00	1
	51st ST.	
	76' LT. STA. 102+50	1
	78' RT. STA. 102+50	1
	46' LT. STA. 104+50	1
	TOTAL	21
B2004120	TREE, MALUS PRAIRIFIRE (PRAIRIFIRE CRABAPPLE), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH
	85TH AVENUE WEST	
	PER LANDSCAPE PLANS	3
	TOTAL	3
	SHRUB, RHUS TYPHINA BAILTIGER (TIGER EYE SUMAC) CONTAINER GROWN, 5-GALLON	EACH
	85TH AVENUE WEST	
	PER LANDSCAPE PLANS	2
	TOTAL	2
K0030412	PERENNIAL PLANTS, STELLA DE ORO DAYLILIES, 1 GALLON POTS	UNIT
	85TH AVENUE WEST (PER LANDSCAPE PLANS)	50
	TOTAL	50
XX003239	CALAMAGROSTIS ACUTIFLORA 'KARL FOERSTER' 2 GAL	EACH
	85TH AVENUE WEST (PER LANDSCAPE PLANS)	14
	TOTAL	14
XX004465	ANNUAL PLANTS	EACH
	85TH AVENUE WEST (PER LANDSCAPE PLANS)	100
	TOTAL	100

XX005307	TREE QUERCUS BICOLOR (SWAMP WHITE OAK), 3" CALIPER, BALLED & BURLAPPED	EACH
	85TH AVENUE WEST	
	166' LT. STA. 10+85	1
	195' LT. STA. 11+10	1
	159' LT. STA. 11+20	1
	40' LT. STA. 12+00	1
	74' LT. STA. 12+10	1
	47' LT. STA. 12+40	1
	36' LT. STA. 14+00	1
	36' LT. STA. 16+00	1
	36' LT. STA. 18+00	1
	36' LT. STA. 20+00	1
	65' LT. STA. 22+00	1
	65' LT. STA. 24+00	1
	49' LT. STA. 27+00	1
	49' LT. STA. 29+00	1
	49' LT. STA. 31+00	1
	49' LT. STA. 33+00	1
	49' LT. STA. 35+00	1
	49' LT. STA. 37+00	1
	49' LT. STA. 39+00	1
	43' LT. STA. 69+00	1
	43' LT. STA. 71+00	1
	51st ST.	
	69' LT. STA. 103+50	1
	48' RT. STA. 103+50	1
	TOTAL	23

LOCATION	EARTH EXCAVATION (C.Y.)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%) (C.Y.)	EMBANKMENT (C.Y.)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (C.Y.)	TOPSOIL FURNISH AND PLACE, 4" (S.Y.)
<b>85TH AVENUE</b>					
LT & RT STA. 10+77.81 - 26+00	931	698	9,694	-8,996	6,837
LT & RT STA. 26+00 - 47+64	3,173	2,380	5,504	-3,124	9,813
LT & RT STA. 48+26 - 75+50	11,004	8,253	2,994	5,259	8,867
SUB TOTAL:	15,108	11,331	18,192	-6,861	25,517
<b>OLD 85TH AVENUE</b>					
LT & RT STA. 0+25 - 2+75	585	439	1	438	1,414
SUB TOTAL:	585	439	1	438	1,414
<b>51st STREET</b>					
LT & RT STA. 100+00 - 100+75	138	104	37	67	225
LT & RT STA. 101+25 - 104+89.26	2,199	1,649	5,418	-3,769	3,756
SUB TOTAL:	2,337	1,753	5,455	-3,702	3,981
<b>42nd STREET</b>					
LT & RT STA. 2+50 - 3+05.50	243	182	0	182	99
SUB TOTAL:	243	182	0	182	99
<b>TURKEY HOLLOW TURN LANE</b>					
RT 200+00 - 205+00	275	206	165	41	728
SUB TOTAL:	275	206	165	41	728
GRAND TOTAL:	18,548	13,911	23,813	-9,902	31,739
CODE NUMBER	20200100			20400800	21101615
PAY ITEM	EARTH EXCAVATION			FURNISHED EXCAVATION	TOPSOIL FURNISH AND PLACE, 4"

No.	REVISIONS DESCRIPTION	DATE



85th Ave. West  
 ROCK ISLAND, ILLINOIS  
**SCHEDULE OF QUANTITIES**

Missman Project No:  
 A04T023  
 File Name:  
 2037A\_SUM&SCH.dwg  
 © COPYRIGHT 2003  
 ALL RIGHTS RESERVED  
 Drawn By: WEF  
 Checked By: DRM  
 Date: MAY, 2006  
20
 Sheet 20 of 94

G:\PI\200A\A04T023-85AVE\_WEST\img\2037A\_SUM&SCH.dwg, 6/6/2006 8:47:48 AM