F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8996	05-00221-00-BR	MADISON	20	7
STA. 275+50	TO STA. 280+00			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
REMOVAL & EROSION CONTROL PLAN				

CONTRACT NO. 97281

	BY	DATE
FINAL SURVEY	SURVEYED	
	PLOTTED	
NOTE BOOK	TEMPLATE	
NO.	AREAS CHECKED	

	BY	DATE
ORIGINAL SURVEY	SURVEYED	
	PLOTTED	
NOTE BOOK	TEMPLATE	
NO.	AREAS CHECKED	

EXIST ROW

EXIST ROW

EXIST ROW

+85.22 ℄ C.E.
28.0' AGG.

+79.06 ℄ C.E.
28' CONC.

19 FT PERIMETER EROS BAR
56 SQ FT SIDEWALK REM
21 FOOT COMB
CURB GUTTER REM

BLACK CREEK

18 SQ FT SIDEWALK REM
3 FOOT COMB
CURB GUTTER REM
17 SQ YD PAVEMENT REM
12 FT PERIMETER EROS BAR
52 FOOT GUARDRAIL REMOV

C1 CURVE DATA
PI STA. 282+32.14
Δ =4°25'
T =358.52
R =9297.20
L =716.68
E =6.91
PC STA. 278+73.62
PT STA. 285+90.30
S.E. = NONE (MATCH EXISTING)

275+00 276+00 277+00 278+00 279+00 280+00 C1 281+00

100'

64'

+50

PROPOSED ℄ HUMBERT ROAD

1541 SQ YD BIT
SURF REM VAR DP

7 SQ FT MEDIAN REMOVAL (PD)
17 SQ YD PAVEMENT REM
52 FOOT GUARDRAIL REMOV
13 FT PERIMETER EROS BAR

EXIST ROW

3 FOOT COMB
CURB GUTTER REM

12 SQ FT SIDEWALK REM

+07

+56

PC = 278+73.62

EXIST ROW

1 EA FR & GRATES REMOVED
814 SQ YD BIT
SURF REM VAR DP
145 SQ FT MEDIAN REMOVAL (PD)

13 FT PERIMETER EROS BAR
13 SQ FT SIDEWALK REM
3 FOOT COMB
CURB GUTTER REM

EXIST ROW

EXIST ROW

STA. 275+50 TO STA. 280+00
34 RAISED REF PVT MK REM

– PAVEMENT REMOVAL

– SIDEWALK REMOVAL

– BITUMINOUS SURFACE REMOVAL
(VARIABLE DEPTH)

– CONCRETE MEDIAN SURFACE REMOVAL

N

0 20' 40'

GRAPHIC SCALE
1" = 20'