CONTRACT NO. 98948

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	WILLIAMSON	55	5
STA. _____		TO STA._____		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

* [X1-(4,4-1,5,6,6-2)] R-1

SHEET 2 OF 2

SUMMARY OF QUANTITIES

	CODE NUMBER	ITEM DESCRIPTION / CONSTRUCTION TYPE CODE	90% FEDERAL / 10% STATE WILLIAMSON COUNTY UNIT	TOTAL QUANTITY	ROADWAY I 000
	44213200	SAW CUTS	FOOT	3,784	3,784
	48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	17,683	17,683
*	63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	938	938
*	63001105	FURNISH AND INSTALL GUARDRAIL BLOCKS	EACH	134	134
*	63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	1	1
*	63100089	TRAFFIC BARRIER TERMINAL TYPE 6B	EACH	3	3
*	63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	3	3
	63200310	GUARDRAIL REMOVAL	FOOT	739	739
*	63300900	VERTICAL ADJUSTMENT OF GUARD RAIL	FOOT	783	783
	63500105	DELINEATORS	EACH	42	42
	63500120	DELINATOR REMOVAL	EACH	40	40
	64200105	SHOULDER RUMBLE STRIP	FOOT	80,650	80,650
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8
	67100100	MOBILIZATION	L SUM	1	1
	70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2	2
	70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	50	50
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3,229	3,229
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,076	1,076
*	72000100	SIGN PANEL - TYPE 1	SQ FT	909	909
*	72900110	METAL POST - TYPE A	EACH	88	88
	78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	80,451	80,451
	78003135	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6", SPECIAL	FOOT	10,136	10,136
	78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	271	271
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	501	501
*	78200420	GUARDRAIL MARKERS, TYPE B	EACH	26	26
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	501	501
*	80300100	LOCATING UNDERGROUND CABLE	FOOT	60	60
*	81000400	CONDUIT IN TRENCH, 1 1/4" DIA., GALVANIZED STEEL	FOOT	72	72
*	81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	60	60
*	81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	63	63
*	81400100	HANDHOLE	EACH	3	3
*	81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	152	152
*	88600100	DETECTOR LOOP, TYPE I	FOOT	175	175
	X0325570	CHANGEABLE MESSAGE SIGN, SPECIAL	CAL DA	42	42
	X0325571	TRAFFIC CONTROL SUPERVISOR	CAL DA	42	42

* SPECIALTY ITEM

Rev.

PLOT DATE = 8/22/2006
FILE NAME = c:\pw_work\PW16285\d9816285sch-m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = thomsskf