

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	WILLIAMSON	55	12
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

* CX1-(4,4-1,5,6,6-2) R-1

RESURFACING AND SHOULDER SCHEDULE

LOCATION STATION TO STATION	BITUMINOUS SURFACE REMOVAL 1 1/2"	BITUMINOUS SURFACE REMOVAL 4"	BIT SURFACE REMOVAL VAR DEPTH	BIT SURFACE REMOVAL BUTT JOINT	RUBBLIZE PCC PAVEMENT	POLYMERIZED BIT CONCRETE BINDER COURSE	POLYMERIZED BIT CONCRETE SURFACE COURSE	BITUMINOUS MATERIALS PRIME COAT, SPECIAL	BITUMINOUS MATERIALS PRIME COAT	SHOULDERS		SHOULDER RUMBLE STRIP	TEMPORARY RAMP
										AGGREGATE TYPE B, SPL	BITUMINOUS (SUPERPAVE)		
	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TONS	TONS	GAL	GAL	SQ YD	TONS	FOOT	SQ YD
NORTHBOUND													
287+46.45 TO 289+26.45				356		16	54	83		80	63	360	
289+26.45 TO 0+00													
0+00 TO 57+43.55		15529			15316	5826	1728	2553	4901	2553	2573	11487	
57+43.55 TO 57+46.55													
57+46.55 TO 79+50		5957			5876	2235	663	979	1880	980	987	4407	
79+50 TO 81+50		533	356			139	60	123		89	70	400	
81+50 TO 81+90		108	71			12	12	20			8	80	
81+90 TO 83+70		480	320			125	54	110		80	63	360	
83+70 TO 157+95.58		20077			19802	7532	2234	3300	6337	3301	3327	14851	
157+95.58 TO 157+96.05													
157+96.05 TO 163+40		1471	400	178	1451	567	208	242	464	242	244	1088	
163+40 TO 165+60		587	391			153	66	135		98	77	440	
165+60 TO 167+30		460	302			52	51	86			34	340	
167+30 TO 168+30			356	89		53	42	54		45	32	200	
168+30 TO 192+30													
192+30 TO 194+00			356	356	213	168	51	87		76	76	340	
194+00 TO 226+30		8733			8613	3276	972	1436	2756	1436	1447	6460	
226+30 TO 228+16.5		497	332			129	56	114		83	65	373	
228+16.5 TO 229+15			101									23	
229+15 TO 231+50		635	418			448	115	529		105		470	
231+50 TO 253+10		5840			5760	2191	650	960	1843	960	968	4320	
253+10 TO 254+90		480	320			125	54	110		80	63	360	
254+90 TO 255+25		95	62			11	11	18			7	70	
255+25 TO 257+25		533	356			139	60	123		89	70	400	
257+25 TO 347+00.75		24268			23935	9105	2700	3989	7659	3990	4022	17952	
347+00.75 TO 348+43.15													
348+43.15 TO 361+50		3533			3485	1326	393	581	1115	581	586	2614	
361+50 TO 363+40		507	338			132	57	117		85	66	380	
363+40 TO 363+80		108	71			12	12	20			8	80	
363+80 TO 365+30		400	267			104	45	92		67	52	300	
365+30 TO 419+74.18		14719			14518	5522	1638	2420	4646	2420	2439	10888	
419+74.18 TO 1461+00													
1461+00 TO 1465+00		1081			1067	406	120	178	341	178	179	800	
1465+00 TO 1466+80				356		16	54	83		80	63	360	31
JOHNSTON CITY ENTRANCE RAMP													
149+64.0 TO 155+79.0	1187					266	133	154					
155+79.0 TO 157+60.0	282					63	32	72		26	69		
157+60.0 TO 158+50.0	140					13	16	34		40	25		29
TOTALS	1,609	106,631	4,817	1,335	100,036	40,162	12,341	18,802	31,942	17,764	17,706	80,180	60

PLOT DATE = 8/19/2006
 FILE NAME = C:\pwork\98948\resurf\resurf.dwg
 USER NAME = ahpardgd