

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	WILLIAMSON	55	14
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS	FED. AID PROJECT	

* (X1-(4,4-1,5,6,6-2)) R-1

PAVEMENT MARKING SCHEDULE

LOCATION STATION TO STATION	PREFORMED LINE 6" SKIP DASH WHITE FOOT	PREFORMED PAVEMENT MARKING			SHORT TERM PAVEMENT MARKING EDGELINE DIAGONALS FOOT	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL EACH	RAISED REFLECTIVE PAVEMENT MARKERS EACH	WORK ZONE PAVEMENT MARKING REMOVAL SQ FT
		LINE 4"		LINE 8"				
		SOLID WHITE FOOT	SOLID YELLOW FOOT	SOLID WHITE FOOT				
NORTHBOUND								
287+46.45 TO 289+26.45	45	180	180		14	2	2	5
289+26.45 TO 0+00								
0+00 TO 57+43.55	1436	5744	5744		459	72	72	153
57+43.55 TO 57+46.55								
57+46.55 TO 79+50	551	2203	2203		176	28	28	59
79+50 TO 83+70	105	420	420		34	5	5	11
83+70 TO 157+95.58	1856	7426	7426		594	93	93	198
157+95.58 TO 157+96.05								
157+96.05 TO 163+40	136	544	544		44	7	7	15
163+40 TO 168+30	123	490	490		39	6	6	13
168+30 TO 192+30								
192+30 TO 226+30	850	3400	3400		272	43	43	91
226+30 TO 228+17	47	187	187		15	2	2	5
228+16.5 TO 229+15								
229+15 TO 231+50	59	235	235		19	3	3	6
231+50 TO 253+10	540	2160	2160		173	27	27	58
253+10 TO 257+25	104	415	415		33	5	5	11
257+25 TO 347+00.75	2244	8976	8976		718	112	112	239
347+00.75 TO 348+43.15								
348+43.15 TO 361+50	327	1307	1307		105	16	16	35
361+50 TO 365+30	95	380	380		30	5	5	10
365+30 TO 419+74.18	1361	5444	5444		436	68	68	145
419+74.18 TO 1461+00								
1461+00 TO 1465+00	100	400	400		32	5	5	11
1465+00 TO 1466+80	45	180	180		14	2	2	5
JOHNSTON CITY ENTRANCE RAMP								
151+25.0 TO 155+79.0	114							
155+79.0 TO 158+50.0		271		271	22			7
TOTALS	10,138	40,362	40,091	271	3,229	501	501	1,077
		80,453						

PLOT DATE = 8/13/2006
 FILE NAME = c:\projects\98948\98948.dwg
 USER = shepardg