

F. A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
885	*	POPE	16	3
STA. 709+74.60		TO STA. 714+62.27		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

**SUMMARY OF QUANTITIES**

\* - D-9 BSMART FY 07-1

RURAL - POPE COUNTY  
SN 076-0007

80% FED 20% STATE  
SFTY-2A

CODE NUMBER	ITEM DESCRIPTION	CONSTRUCTION TYPE CODE	UNIT	QUANTITY
X0301245	SHOULDER REMOVAL		SQ YD	78
X0320887	POLYMER CONCRETE		CU FT	31.0
X0321468	PLUG EXISTING DECK DRAINS		EACH	56
X0321743	SILICONE JOINT SEALER, 1"		FOOT	198
X0322194	POLYMER MODIFIED PORTLAND CEMENT MORTAR		SQ FT	8.5
X0325305	STRUCTURAL REPAIR OF CONCRETE (< 5')		SQ FT	226
X7015000	CHANGEABLE MESSAGE SIGN		CAL MO	1
XZ191205	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 3"		SQ YD	1148
Z0002600	BAR SPLICERS		EACH	34
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"		SQ YD	1146
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)		SQ YD	0.4
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TL-3		EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TL-3		EACH	2
Z0073400	TEMPORARY SUPPORT SYSTEM		EACH	12
28100205	STONE RIPRAP, CLASS A3		TON	48
28200200	FILTER FABRIC		SQ YD	95
35600500	BITUMINOUS CONCRETE BASE COURSE WIDENING 10 INCHES		SQ YD	78
44000910	BITUMINOUS CONCRETE REMOVAL (DECK)		SQ YD	1194
50102400	CONCRETE REMOVAL		CU YD	15.3
50300255	CONCRETE SUPERSTRUCTURE		CU YD	18.1
50300300	PROTECTIVE COAT		SQ YD	1403
50300260	BRIDGE DECK GROOVING		SQ YD	1121
50800205	REINFORCEMENT BARS, EPOXY COATED		POUND	1900
50900105	ALUMINUM RAILING, TYPE L		FOOT	80
67000400	ENGINEER'S FIELD OFFICE, TYPE A		CAL MO	4
67100100	MOBILIZATION		L SUM	1
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)		EACH	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201		L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS		EACH	1
70106700	TEMPORARY RUMBLE STRIP		EACH	33
70300100	SHORT-TERM PAVEMENT MARKING		FOOT	130
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"		FOOT	2040
70301000	WORK ZONE PAVEMENT MARKING REMOVAL		SQ FT	238
70400100	TEMPORARY CONCRETE BARRIER		FOOT	520
70400200	RELOCATE TEMPORARY CONCRETE BARRIER		FOOT	510
* 78001110	PAINT PAVEMENT MARKING - LINE 4"		FOOT	1149

© SFTY-3N  
\* SPECIALTY ITEMS

Prepared By: *Joe Zolman*  
DISTRICT STUDIES & PLANS ENGINEER  
Examined By: *James Lewis Emery*  
DISTRICT LAND ACQUISITION ENGINEER  
Examined By: *Candi Nelson*  
DISTRICT PROGRAM DEVELOPMENT ENGINEER  
Examined By: *Kevin Hamm*  
DISTRICT OPERATIONS ENGINEER  
Examined By: *Joseph Lopez*  
DISTRICT CONSTRUCTION ENGINEER  
Examined By: *Bruce Gooden*  
DISTRICT MATERIALS ENGINEER  
Examined By: *John Smith*  
DISTRICT PROJECT SUPERVISION ENGINEER  
Examined By: *James Lewis Emery*  
ASSISTANT REGIONAL ENGINEER  
Approved By: *Mark C. Williams*  
DEPUTY DIRECTOR OF HIGHWAYS, REGION ENGINEER  
DATE: *July 20 2007*

Rev.

PLOT DATE = 6/26/2008  
FILE NAME = QAPProgram  
PLOT SCALE = 48,9999 / 1  
USER NAME = halsstead