

TRANSPORTATION BULLETIN



Illinois Department of Transportation

ADDENDUM NO. 1

Dated: September 20, 2006

For: Transportation Bulletin

Letting Date: September 22, 2006

Volume 9 No. 33 Dated: August 18, 2006

Item No. 1A – Extend Municipal Water Service to Airport for Fire Protection.

Pontiac Municipal Airport
Pontiac, Illinois
Livingston County
IL Project No.: PNT-3397
Contract No.: PO015

REASON FOR ADDENDUM:

1. Clarification of bidding documents.
2. Revised Proposal Document completion schedule.
3. Revised Schedule of Prices.
4. Revised Special Provisions.

TO ALL PLAN HOLDERS:

1. Consider the following comments and clarifications when bidding this project -
 - The reference to 8"x6" tees at Stations 264+73.5 and 301+24 are standard 8"x8"x6" tees. Reducers to be used as necessary.
 - At Station 301+24, terminate the main with a plug on the tee. The domestic service for the airport will be connected to the main with a standard tapping saddle.
 - The lateral valves should be moved to 3 feet from the hydrants at Stations 264+73.5 and 301+24.

- Relocate the following valves as indicated:
 From Station 212+50 to 214+55 (just east of the hydrant).
 From Station 222+75 to 222+90 (just east of the hydrant).
 From Station 235+40 to 235+45 (just east of the hydrant).
 From Station 238+05 to 241+90 (midway between nearest valves).
- Please add gate valves at the following locations:
 12" gate valve at Station 248+00.
 2 - 8" gate valves at Station 261+33.
 8" gate valve at Station 264+50.
- Please refer to the attached material list of equipment to be provided by the City of Pontiac for this contract.

2. Revised contract completion schedule

Page 25 of the Proposal Document should be revised as follows:

Section 13. CONTRACT TIME. The contract time for this project is 60 calendar days and is based on an anticipated notice-to-proceed date of October 30, 2006.

3. Revised Schedule of Prices

The attached revised Schedule of Prices dated 9/19/06 should be completed and returned with the bid.

4. Revise the following Special Provision Section 760 – 3.3-Add the following on page 9 after the first paragraph:

All fittings and valves are to be restrained with Field Lok Joints and gaskets per pipe manufacturers installation recommendations.

- Revise Plan Sheet 2 – Summary of Quantities

Item No. AR760830 Revise "water valve-6"" to read "water valve"
 Revise quantity to "16 EA".
 Delete Item No. AR760831

- Special Provision Section 760830-5.1

After the sentence "payment will be made under"
 Revise to Read
 "Item AR760830-Water valve per Each"

COUNTY NAME LIVINGSTON	CODE 105	DIST 03	AIRPORT NAME PONTIAC MUNICIPAL	FED PROJECT -	ILL PROJECT PN-T -3397
---------------------------	-------------	------------	-----------------------------------	------------------	---------------------------

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR501508	8" PCC PAVEMENT	S.Y.	25.000 X	-	-	-	-
AR701830	TRENCH BACKFILL	C.Y.	65.000 X	-	-	-	-
AR760502	2" DUCTILE IRON WATER MAIN	L.F.	5.000 X	-	-	-	-
AR760506	6" DUCTILE IRON WATER MAIN	L.F.	160.000 X	-	-	-	-
AR760508	8" DUCTILE IRON WATER MAIN	L.F.	490.000 X	-	-	-	-
AR760512	12" DUCTILE IRON WATER MAIN	L.F.	6,100.000 X	-	-	-	-
AR760520	20" DUCTILE IRON WATER MAIN	L.F.	41.000 X	-	-	-	-
AR760800	FIRE HYDRANT	EACH	6.000 X	-	-	-	-
AR760810	WATER METER	EACH	1.000 X	-	-	-	-
AR760830	WATER VALVE	EACH	16.000 X	-	-	-	-
AR760999	WELL ABANDONMENT	EACH	2.000 X	-	-	-	-
AR901510	SEEDING	ACRE	0.300 X	-	-	-	-

TOTAL \$

NOTE:
 *** PLEASE TURN PAGE FOR IMPORTANT NOTES ***

NOTE:

1. EACH PAY ITEM SHOULD HAVE A UNIT PRICE AND A TOTAL PRICE.
2. THE UNIT PRICE SHALL GOVERN IF NO TOTAL PRICE IS SHOWN OR IF THERE IS A DISCREPANCY BETWEEN THE PRODUCT OF THE UNIT PRICE MULTIPLIED BY THE QUANTITY.
3. IF A UNIT PRICE IS OMITTED, THE TOTAL PRICE WILL BE DIVIDED BY THE QUANTITY IN ORDER TO ESTABLISH A UNIT PRICE.
4. A BID MAY BE DECLARED UNACCEPTABLE IF NEITHER A UNIT PRICE NOR A TOTAL PRICE IS SHOWN.

Pontiac Municipal Airport Watermain Cost Estimate
MATERIAL LIST PROVIDED BY THE CITY OF PONTIAC

Item	Description	Quantity	Unit
1	12" Ductile Iron Watermain PC 350 w/ Field Lok or Tyton Joint gaskets	6100	LF
2	8" Ductile Iron Watermain PC 350 w/ Field Lok or Tyton gaskets	490	LF
3	6" Ductile Iron Watermain PC 350 w/ Field Lok or Tyton Joint gaskets	160	LF
4	2" Ductile Iron Watermain PC 350 w/ Field Lok or Tyton Joint gaskets	5	LF
5	20" Ductile Iron Casing	106	LF
6	12" Gatevalve & Valve Box	7	EA
7	8" Gatevalve & Valve Box	3	EA
8	6" Gatevalve & Valve Box	6	EA
9	6" Fire Hydrant	6	EA
10	Polyethylene Encasement 12"	6100	LF
11	Polyethylene Encasement 8"	490	LF
12	Polyethylene Encasement 6"	160	LF
13	Water Meter	1	EA
14	12" - 22 1/2' DI Bend	2	EA
15	12" - 45' DI Bend	5	EA
16	12"x 12" X 6" DI Tee	4	EA
17	12" x 12" X 12" DI Tee	1	EA
18	12" Plug	1	EA
19	12" - 90' Bend	1	Ea
20	12"x 12" X 8"	1	EA
21	8" x 8" X 6" Tee	2	EA
22	12" x 8" Reducer	1	EA
23	2" - 90' Bend	1	EA
24	6" - 45' Bend	1	EA
25	8" Plug	2	EA