

Q1057


DATE	REVISION	BY

SUMMARY OF QUANTITIES


ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR108158	1/C #8 5 KV UG CABLE IN UD	L.F.	1,171	
AR125510	MIRL, BASE MOUNTED	EACH	2	
AR125545	MI THRESHOLD LIGHT BASE MTD	EACH	8	
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	20	
AR125931	REPLACE LIGHT LENSE	EACH	2	
AR820520	PAVEMENT MARKING-WATERBORNE	S.F.	82,868	
AR820525	PAVEMENT MARKING-BLACK BORDER	S.F.	15,132	
AR820900	PAVEMENT MARKING REMOVAL	S.F.	82,838	
AR800449	WEED CONTROL LIGHT RING	EACH	10	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	EXISTING MARKING REMOVAL PLAN STA. 100+00 TO STA. 153+98
5	PROPOSED MARKING PLAN STA. 100+00 TO STA. 153+98
6	PROPOSED MARKING DETAILS
7	PROPOSED ELECTRICAL PLAN
8	PROPOSED ELECTRICAL DETAILS
9	PROPOSED ELECTRICAL DETAILS
10	PROPOSED ELECTRICAL NOTES
11	PROPOSED ELECTRICAL NOTES


QUINCY REGIONAL AIRPORT
 BALDWIN FIELD
 ADAMS COUNTY, ILLINOIS
 ILL. PROJ.: UN-3619 A.I.P. PROJ.: 3-17-0085-XX

IEL Project No. 824-06RWD 0240 Revision R-002FLP.DWG Scale NOT TO SCALE Date 06/06/06	LAYOUT DRAWN BAK 06/06/06 REVIEWED CAH 06/15/06
--	---


HANSON
 Hanson Professional Services Inc.
 1625 South State Street
 Springfield, Illinois 62703-2886
 Offices Nationwide

RUNWAY 13-31 SAFETY
 AREA IMPROVEMENTS
 SUMMARY OF QUANTITIES
 AND
 INDEX TO SHEETS