



620900-PAVEMENT MARKING REMOVAL NOTES

THE EXISTING PAVEMENT MARKING SHALL BE REMOVED IN ACCORDANCE WITH ITEM 620 "PAVEMENT MARKING" AS STATED ON PAGE 77 OF THE SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS, ADOPTED JULY 1, 2004.

THE AREAS THAT ARE DESIGNATED FOR REMOVAL ARE SHOWN ON THIS SHEET.

ALL AREAS TO BE REMOVED ARE CALCULATED AREAS. ANY ADDITIONAL AREAS, DUE TO OVER SPRAY, SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

IT WILL BE THE CONTRACTOR'S RESPONSIBILITY TO PICK UP ALL WASTE MATERIAL (SAND, REMOVED PAINT, ETC.) THAT IS DERIVED FROM THE REMOVAL PROCESS AND DISPOSE OF THIS WASTE MATERIAL OFF THE AIRPORT SITE AT THE CONTRACTOR'S OWN EXPENSE. NO MATERIAL WILL BE BROOMED, FLUSHED OR BLOWN ONTO THE PAVEMENT SHOULDER AREA.

THE PROPOSED MARKING REMOVAL WILL BE PAID FOR UNDER ITEM:
AR620900 PAVEMENT MARKING REMOVAL — 82,838 S.F.

- LEGEND**
- EXISTING PAVEMENT
 - EXISTING TAXIWAY MARKING
 - EXISTING RUNWAY MARKING
 - EXISTING MARKING (TO BE REMOVED)

0' 50' 100' 200'
 HALF SIZE SCALE: 1" = 200'
 FULL SIZE SCALE: 1" = 100'

DATE	REVISION	BY

QUINCY REGIONAL AIRPORT
BALDWIN FIELD
ADAMS COUNTY, ILLINOIS

IL. PROJ.: UIN-3619 A.I.P. PROJ.: 3-17-0085-XX

REL. Project No. 824-06RWYD.0240	DATE	BY
File Name: R-151MRK.DWG	06/07/06	CAH
Scale: 1" = 100'	06/07/06	CAH
Date: 06/07/06	06/07/06	CAH

HANSON
 Hanson Professional Services Inc.
 1525 South Sixth Street
 Springfield, Illinois 62703-2898
 Offices Nationwide

RUNWAY 13-31 SAFETY AREA IMPROVEMENTS
 EXISTING MARKING REMOVAL PLAN
 STA. 100+00 TO STA. 153+98