CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE 90% FED 10% STATE ROADWAY 0006	90% FED 10% STATE BRIDGE 0010	90% FED 10% STATE TRAFFIC SIGNALS 0021
25100115	MULCH, METHOD 2	ACRE	1.75	1.75		
25100630	EROSION CONTROL BLANKET	SQ YD	7185	7185		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	22	22		
28000305	TEMPORARY DITCH CHECKS	FOOT	110	110		
28000400	PERIMETER EROSION BARRIER	FOOT	1725	1725		
28000500	INLET AND PIPE PROTECTION	EACH	3	3		
28100107	STONE RIPRAP, CLASS A4	SQ YD	376	376		
28100805	STONE DUMPED RIPRAP, CLASS A3	TON	243	243		
28200200	FILTER FABRIC	SQ YD	607	607		
35101400	AGGREGATE BASE COURSE, TYPE B	TON	549	549		
40200900	AGGREGATE SURFACE COURSE, TYPE B	CU YD	6	6		
40600275	BITUMINOUS MATERIALS (PRIME COAT)	POUND	2866	2866		
40600295	POLYMERIZED BITUMINOUS MATERIALS (TACK COAT)	POUND	21335	21335		
~~40600370~~	~~LONGITUDINAL JOINT SEALANT~~	~~FOOT~~	~~4002~~	~~4002~~		

2

* SPECIALTY ITEM
** 100% STATE
Δ 0042

The Upchurch Group
architects engineers surveyors
Professional Design Firm Corporation License No. 184-003401
123 North 15th Street Mattoon, IL 61938 Phone: 217.235.3177
e-mail: upchurchgroup@upchurchgroup.com

USER NAME = Sta42	DESIGNED - MJS	REVISED -
TUG PROJECT NO. 3120032-10	DRAWN -	REVISED -
PLOT SCALE = 2.0000 ' / in.	CHECKED - MJS	REVISED -
PLOT DATE = 6/21/2023	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
AIRPORT ROAD OVER I-474

SCALE: 2.0000 ' / in. | SHEET 2 OF 13 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
474	(72-3HB-4)BR	PEORIA	175	5

CONTRACT NO. 68886
ILLINOIS FED. AID PROJECT

2 REV. 9/5/23 REV. 7/26/23

MODEL: Default
FILE NAME: P:\Civil_IDOT_DIST4\PTB 194-035 var PH I-474 3120032\WO 10 Airport Road Phase 2 3120032-10\CAD Sheets\0468886-sht-SOQ.dgn

PAVEMENT SCHEDULE

LOCATION	STATION TO STATION		LT / RT	LENGTH	35101400 AGGREGATE BASE COURSE, TYPE B	40600275 BITUMINOUS MATERIALS (PRIME COAT)	40600295 POLYMERIZED BITUMINOUS MATERIALS (TACK COAT)	40600370 LONGITUDINAL JOINT SEALANT	40603080 HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	40603205 POLYMERIZED HMA BINDER COURSE, IL-9.5, N50	40604160 POLYMERIZED HMA SURFACE COURSE, IL-9.5, MIX "D", N50	48203003 HMA SHOULDERS, 1 ½"	48203004 HMA SHOULDERS, 1 3/4"	48203033 HMA SHOULDERS, 9"	X4400196 HMA SURFACE REMOVAL, SPECIAL	Z0034105 MATERIAL TRANSFER DEVICE	Z0062456 TEMPORARY PAVEMENT
				FOOT	TON	POUND	POUND	FOOT	TON	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD	TON	SQ YD
PRESTAGE	188+00	191+50	LT / RT	350													574.9
PRESTAGE	197+25	200+20	LT / RT	295													725.5
AIRPORT RD	184+37	190+00	LT	563		63.3	5773.2	1008			320.2	340.8			89.0	320.2	28.1
AIRPORT RD	184+37	190+00	RT	563		392.6	3155.6	756			159.5	305.0			37.5	159.5	180.1
AIRPORT RD	190+00	192+73.36	LT	273.36	180	692.3	2030.8	274	120.7	65.9	63.3	303.8			27.2	249.9	307.7
AIRPORT RD	190+00	192+73.36	RT	273.36	46	692.3	2249.5	274	120.7	92.8	89.0				27.2	302.5	307.7
AIRPORT RD	192+73.36	193+27	RT	53.64		135.8											60.4
AIRPORT RD	195+74	197+60	RT	186.00		443.2											197.0
AIRPORT RD	196+27.72	198+50	LT	222.28	243	445.9	1526.9	222	201.8	51.0	60.2		198.2		21.6	313.0	197.6
AIRPORT RD	196+27.72	198+50	RT	222.28	80		1471.8	572	210.1	80.0	98.1				21.6	388.2	
AIRPORT RD	198+50	202+98	LT	448			2638.4	448			142.7		397.6		30.9	142.7	75.6
AIRPORT RD	198+50	202+98	RT	448			2488.9	448			161.8		165.9		44.4	161.8	
FAI 474	284+25	285+40	LT	115										38.3			
FAI 474	284+00	285+15	RT	115										38.4			
				TOTALS	549	2865.4	21335.1	4002	653.3	289.7	1094.8	949.6	761.7	76.7	299.4	2037.8	2654.6
				ROUNDED TOTALS	549	2866	21335	4002	654	290	1095	950	762	77	300	1650	2655

2

CURB AND GUTTER & MEDIAN SCHEDULE

LOCATION	STATION TO STATION		LT/RT	60605000 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	60608582 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	60618300 CONCRETE MEDIAN SURFACE, 4 INCH	60622320 CONCRETE MEDIAN, TYPE SM-4.24
				FOOT	FOOT	SQ FT	SQ FT
AIRPORT RD	195+98.36	198+50.00	LT	251.6			
AIRPORT RD	189+00.00	193+24.21	LT		424.6		
AIRPORT RD	189+00.00	193+27.31	RT		427.3		
AIRPORT RD	195+74.19	201+19.02	LT		547.1		
AIRPORT RD	195+76.87	201+19.02	RT		542.2		
AIRPORT RD	201+19.02	201+26.00	LT/RT			67.7	
AIRPORT RD	186+47.30	189+00	LT/RT				1887.1
			TOTALS	251.6	1941.2	67.7	1887.1
			ROUNDED TOTALS	252	1942	68	1888

AGGREGATE SURFACE COURSE, TYPE B SCHEDULE

LOCATION	STATION	LT/RT	AREA	DEPTH	40200900 AGGREGATE SURFACE COURSE, TYPE B
			SQ FT	INCH	CU YD
AIRPORT RD	190+32	LT	280	6.0	5.2
				TOTAL	5.2
				ROUNDED TOTAL	6

SIDEWALK SCHEDULE

LOCATION	STATION TO STATION		LT/RT	42400100 PCC SIDEWALK, 4"
				SQ FT
AIRPORT RD	186+52.94	187+36.57	LT	395.2
			TOTAL	395.2
			ROUNDED TOTAL	396

AGGREGATE SHOULDERS,TYPE B SCHEDULE

LOCATION	STATION TO STATION		LT/RT	AREA	WEDGE DEPTH	48101200 AGGREGATE SHOULDERS, TYPE B
				SQ FT	INCH	TON
AIRPORT RD	190+00.00	190+17.59	LT	75.4	9.0	2.1
AIRPORT RD	190+45.59	193+16.73	LT	1054.6	10.0	33.4
AIRPORT RD	195+68.73	198+50.00	LT	819.5	9.0	23.3
AIRPORT RD	191+18.75	193+32.36	RT	943.3	9.0	26.9
AIRPORT RD	195+84.36	198+50	RT	621.2	9.0	17.7
FAI 474	284+26.58	184+31.58	LT	53.7	9.0	1.5
FAI 474	285+41.04	288+66.69	LT	1567.4	9.0	44.6
FAI 474	284+02.28	284+07.28	RT	53.7	9.0	1.5
FAI 474	285+10.54	285+15.54	RT	44.3	9.0	1.3
					TOTAL	152.3
					ROUNDED TOTAL	153