F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
840	143N	WILL	12	4
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

CONTRACT NO. - 60445

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	FED/ST CONSTRUCTION TYPE CODE 0004 ROADWAY (80/20)	FED/ST 0021 LIGHTING (80/20)	FED/ST/CITY 0021 TRAFFIC SIGNAL (80/10/10)	FED/ST 0021 SIDEWALK (80/20)	FED/ST 0040 RETAINING WALL (80/20)	CITY 0021 PRE-EMPTION EQUIPMENT (100% CITY)	FED/ST 0031 LAND-SCAPING (80/20)
M2020010	EARTHWORK EXCAVATION	CU M	15,731	15,731						
M2020050	EARTH EXCAVATION (WIDENING)	CU M	1584	1584						
M2021200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU M	233	233						
M2070220	POROUS GRANULAR EMBANKMENT	CU M	233	233						
M2080150	TRENCH BACKFILL	CU M	1156	1156						
1 * M2113100	TOPSOIL FURNISH AND PLACE, 100MM	SQ M	4673							4673
M2140100	GRADING AND SHAPING DITCHES	METER	83							83
* M2500210	SEEDING, CLASS 2A	HA	0.07							0.07
* M2500400	NITROGEN FERTILIZER NUTRIENT	KG	36							36
* M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KG	36							36
1 * M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	36							36
* M2510630	EROSION CONTROL BLANKET	SQ M	627							627
* M2520110	SODDING, SALT TOLERANT	SQ M	4046							4046
* M2520200	SUPPLEMENTAL WATERING	UNIT	45							45
M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	8							8
M2800305	TEMPORARY DITCH CHECKS	METER	16							16
M2800400	PERIMETER EROSION BARRIER	METER	1387							1387
M3111100	SUB-BASE GRANULAR MATERIAL, TYPE B 100MM	SQ M	707	707						
M3550500	HOT-MIX ASPHALT BASE COURSE, 200MM	SQ M	574	574						
M3560525	HOT-MIX ASPHALT BASE COURSE WIDENING, 225MM	SQ M	317	317						
M4060200	BITUMINOUS MATERIALS (PRIME COAT)	M TON	9	9						
M4060300	AGGREGATE (PRIME COAT)	M TON	46	46						
M4060400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	M TON	4	4						
M4075275	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH) 275MM	SQ M	1623	1623						
M4063310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	M TON	70	70						
M4063335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	M TON	64	64						
M4075325	HOT-MIX ASPHALT PAVEMENT. (FULL DEPTH) 325MM	SQ M	9362	9362						
M4240125	PORTLAND CEMENT CONCRETE SIDEWALK 125MM	SQ M	1505				1505			
M4063340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	M TON	387	387						

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	FED/ST CONSTRUCTION TYPE CODE 0004 ROADWAY (80/20)	FED/ST 0021 LIGHTING (80/20)	FED/ST/CITY 0021 TRAFFIC SIGNAL (80/10/10)	FED/ST 0021 SIDEWALK (80/20)	FED/ST 0040 RETAINING WALL (80/20)	CITY 0021 PRE-EMPTION EQUIPMENT (100% CITY)	FED/ST 0031 LAND-SCAPING (80/20)
M4400750	HOT-MIX ASPHALT SURFACE REMOVAL, 50MM	SQ M	2021	2021						
M4402000	PAVEMENT REMOVAL	SQ M	8787	8787						
M4402010	DRIVEWAY PAVEMENT REMOVAL	SQ M	576	576						
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	248	248						
M4402050	SIDEWALK REMOVAL	SQ M	372				372			
M4402530	PAVED SHOULDER REMOVAL	SQ M	1425	1425						
M4428230	CLASS D PATCHES, TYPE II, 250 MM	SQ M	190	190						
M4428330	CLASS D PATCHES, TYPE III, 250 MM	SQ M	180	180						
M4428430	CLASS D PATCHES, TYPE IV, 250 MM	SQ M	16	16						
M4812150	AGGREGATE SHOULDERS, TYPE B 150MM	SQ M	289	289						
M4816000	AGGREGATE WEDGE SHOULDER, TYPE B	M TON	23	23						
M4820600	HOT-MIX ASPHALT SHOULDER, 200 MM (8")	SQ M	28	28						
~~MX512205~~	~~FURNISHING SOLDIER PILES HP SECTION~~	~~METER~~	~~261~~					~~261~~		
~~M5080295~~	~~REINFORCEMENT BARS, EPOXY COATED~~	~~KG~~	~~5290~~					~~5290~~		
~~M5090010~~	~~ALUMINUM RAILING, TYPE L~~	~~METER~~	~~85~~					~~85~~		
M542E128	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 600MM	EACH	1	1						
M5500030	STORM SEWERS, CLASS A, TYPE 1 300MM	METER	58	58						
M5500045	STORM SEWERS, CLASS A, TYPE 1 400MM	METER	99	99						
M5500055	STORM SEWERS, CLASS A, TYPE 1 500MM	METER	125	125						
M5500430	STORM SEWERS, CLASS A, TYPE 2 300MM	METER	474	474						
M5500455	STORM SEWERS, CLASS A, TYPE 2 500MM	METER	119	119						
M5500465	STORM SEWERS, CLASS A, TYPE 2 600MM	METER	82	82						
M6010605	PIPE UNDERDRAINS 100MM	METER	110	110						
M6020180	CATCH BASINS, TYPE A, 1.2M DIAMETER, TYPE 23 FRAME AND GRATE	EACH	36	36						
M6021405	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1						
M6021410	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	23	23						
M6060500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.30	METER	1276	1276						
M6063600	CONCRETE MEDIAN SURFACE, 100 MM (4")	SQ M	36	36						
1 * M6690200	NON-SPECIAL WASTE DISPOSAL	CU M	200	200						
M7030100	SHORT-TERM PAVEMENT MARKING	METER	526	526						

1 * Specialty Items

1 Rev. 7-26-11

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
IL. 50 AT COURT STREET
Rev.

PLOT DATE: 5/20/2011

5/20/2011
p:\new work flow\dgn's\plan\840143N2478P1102297-sht-rx.plan.dgn