

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	80% FED. 20% STATE URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				ROADWAY 0004	BRIDGE 0014
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4,865	4,865	0
70400100	TEMPORARY CONCRETE BARRIER	FOOT	590	590	0
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	590	590	0
72000300	SIGN PANEL - TYPE 3	SQ FT	791	791	0
72400730	RELOCATE SIGN PANEL - TYPE 3	SQ FT	311	311	0
73304000	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT	67	67	0
73602000	REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	EACH	4	4	0
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	11,232	11,232	0
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	61	61	0
78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	36.4	36.4	0.0
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	7,724	7,724	0
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	110	110	0
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	72	72	0
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	16	16	0
78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	8	8	0
78200410	GUARDRAIL MARKERS, TYPE A	EACH	28	28	0
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2	0
78300100	PAVEMENT MARKING REMOVAL	SQ FT	6,472	6,472	0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	72	72	0
81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	525	525	0
81100805	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., PVC COATED GALVANIZED STEEL	FOOT	80	80	0
81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	14	14	0
81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	2	2	0
81300730	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16" X 14" X 6"	EACH	2	2	0
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	1,975	1,975	0
81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	245	245	0
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	735	735	0
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	245	245	0
82107200	UNDERPASS LUMINAIRE, 100 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	8	8	0
X0325541	REMOVE EXISTING LIGHTING SYSTEM	L SUM	1.0	1.0	0.0
X0018800	DRAINAGE SYSTEM	L SUM	1.0	0.0	1.0
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	36	0.0	36
X6060500	CORRUGATED MEDIAN REMOVAL	SQ FT	3,412	3,412	0
X6640304	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	FOOT	152	152	0
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1.0	1.0	0.0

CODE NO.	ITEM	UNIT	80% FED. 20% STATE URBAN TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				ROADWAY 0004	BRIDGE 0014
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1.0	1.0	0.0
X7030025	WET REFLECTIVE TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS	SQ FT	36	36	0
X7030030	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	14,485	14,485	0
X7200056	TEMPORARY SIGN PANEL ASSEMBLY	SQ FT	311	311	0
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	20	0	20
Z0004552	APPROACH SLAB REMOVAL	SQ YD	274	274	
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	664	0	664
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.0	1.0	0.0
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	12	0	12
Z0018004	DRAINAGE SCUPPERS, DS-12	EACH	2	0	2
Z0026407	TEMPORARY SHEET PILING	SQ FT	141	0	141
Z0030280	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 3	EACH	2	2	0
Z0030360	IMPACT ATTENUATORS, RELOCATE (SEVERE USE), TEST LEVEL 3	EACH	2	2	0
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51	51	0
Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	6	6	0
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	69	0	69
Z0062456	TEMPORARY PAVEMENT	SQ YD	379	379	0
<i>Z0100200</i>	<i>TEMPORARY RAISED REFLECTIVE PAVEMENT MARKERS</i>	<i>EACH</i>	<i>25</i>	<i>25</i>	
<i>X7013820</i>	<i>TRAFFIC CONTROL SURVEILLANCE (EXPRESSWAYS)</i>	<i>CAL DAY</i>	<i>10</i>	<i>10</i>	

* SPECIALTY ITEMS

FILE NAME = G:\projects\2102155_00A\040D\Civil\Sh\3\3\686868-03aht-500.dgn



USER NAME = zpmurd	DESIGNED - DJB	REVISED -
PLOT SCALE = 50.00' / IN.	DRAWN - ENTRAN	REVISED -
PLOT DATE = 7/6/2011	CHECKED - TMH	REVISED -
	DATE - 06/15/11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**FAI ROUTE 57 (INTERSTATE 57) AT FAU ROUTE 3778 (CRAWFORD AVENUE)
SUMMARY OF QUANTITIES**

SCALE: 50.00' / IN. SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE. 57	SECTION 1112.1B	COUNTY COOK	TOTAL SHEETS 75	SHEET NO. 4
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60863	

Rev.