

				CONSTRUCTION CODE							
				100% LAKE COUNTY						100% VILLAGE OF LIBERTYVILLE	100% IDOT
				ROADWAY	SN-049-0199	BOX CULVERT	RETAINING WALL	TRAFFIC SIGNALS	LIGHTING URBAN		
				0003	BRIDGE	0040	0040	0021	0021		
				URBAN	0010	URBAN	URBAN	URBAN			
				URBAN	URBAN	URBAN	URBAN	URBAN			
CODE NO.	ITEM	UNIT	TOTAL QUANTITY								
28100103	STONE RIPRAP, CLASS A2	SQ YD	22	22							
28100105	STONE RIPRAP, CLASS A3	SQ YD	518	518							
28100203	STONE RIPRAP, CLASS A2	TON	6	6							
28200200	FILTER FABRIC	SQ YD	540	540							
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SQ YD	112173	112173							
35101400	AGGREGATE BASE COURSE, TYPE B	TON	1666	1666							
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	4705	4705							
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5236	5236							
40600300	AGGREGATE (PRIME COAT)	TON	13	13							
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	2500	2500							
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	200	200							
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1133	1133							
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	396	396							
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	89602	89602							
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	1402	1402							
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	312	312							
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	100110	100110							
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	160	160							
42400800	DETECTABLE WARNINGS	SQ FT	16	16							
44000100	PAVEMENT REMOVAL	SQ YD	56761	56761							
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	2159	2159							
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	8621	8621							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	11806	11806							
44000600	SIDEWALK REMOVAL	SQ FT	5362	5362							
44004250	PAVED SHOULDER REMOVAL	SQ YD	3245	3245							
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	60	60							
48101100	AGGREGATE SHOULDERS, TYPE A 12"	SQ YD	50	50							
48300415	PORTLAND CEMENT CONCRETE SHOULDERS 9 3/4"	SQ YD	608	608							
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1					
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1			1					
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1			1					
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1			1					
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH	1	1							
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1			1					
50102400	CONCRETE REMOVAL	CU YD	81			81					

• SPECIALITY ITEM

FILE NAME =	USER NAME = IDOT	DESIGNED - EJM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
\\102901\cadd\sheet\sh-t-soq002.dgn		DRAWN - BK	REVISED -						330	128R-3	LAKE	518	6
PLOT SCALE = 50.0000' / IN.	CHECKED - CFL	REVISOR -	REVISOR -		CONTRACT NO. 60953								
PLOT DATE = 8/12/2011	DATE - 12/17/10	REVISOR -	REVISOR -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT		