

				CONSTRUCTION CODE								
				100% LAKE COUNTY							100% VILLAGE OF LIBERTYVILLE 0043	100% IDOT 0043
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0003 URBAN	SN-049-0199 BRIDGE 0010 URBAN	BOX CULVERT 0040 URBAN	RETAINING WALL 0040 URBAN	TRAFFIC SIGNALS 0021 URBAN	LIGHTING URBAN 0021			
50104400	CONCRETE HEADWALL REMOVAL	EACH	7	7								
50105220	PIPE CULVERT REMOVAL	FOOT	1528	1528								
50200100	STRUCTURE EXCAVATION	CU YD	3159		1572		1587					
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	7925			3325	4600					
50300100	FLOOR DRAINS	EACH	8		8							
50300225	CONCRETE STRUCTURES	CU YD	1254.6		532.4		722.2					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	617.5		467.3		150.2					
50300260	BRIDGE DECK GROOVING	SQ YD	529		529							
50300285	FORM LINER TEXTURED SURFACE	SQ FT	9154			926	8228					
50300300	PROTECTIVE COAT	SQ YD	1544		1272		272					
50500305	ERECTING STRUCTURAL STEEL	L SUM	1		1							
50500505	STUD SHEAR CONNECTORS	EACH	6997		3597		3400					
50800105	REINFORCEMENT BARS	POUND	70540			70540						
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	278010		157220	1930	118860					
50800515	BAR SPLICERS	EACH	841		713	128						
50901750	PARAPET RAILING	FOOT	638		130		508					
51200958	FURNISHING METAL SHELL PILES 14" X 0.250"	FOOT	2535		2535							
51202305	DRIVING PILES	FOOT	2535		2535							
51203200	TEST PILE METAL SHELLS	EACH	2		2							
51204650	PILE SHOES	EACH	149		149							
51500100	NAME PLATES	EACH	3		1	2						
52000110	PREFORMED JOINT STRIP SEAL	FOOT	190		190							
52100210	ERECTING ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	11		11							
52100520	ANCHOR BOLTS, 1"	EACH	22		22							
54003000	CONCRETE BOX CULVERTS	CU YD	386			386						
54010402	PRECAST CONCRETE BOX CULVERTS 4' X 2'	FOOT	184			184						
54010503	PRECAST CONCRETE BOX CULVERTS 5' X 3'	FOOT	99			99						
54010706	PRECAST CONCRETE BOX CULVERTS 7' X 6'	FOOT	222			222						
54010803	PRECAST CONCRETE BOX CULVERTS 8' X 3'	FOOT	116			116						
54010804	PRECAST CONCRETE BOX CULVERTS 8' X 4'	FOOT	107			107						
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	7	7								
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 19"	EACH	10	10								
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	1	1								

\* SPECIALITY ITEM

FILE NAME =	USER NAME = IDOT	DESIGNED - EJM	REVISED -
\\102901\cadd sheets\sh-t-soq003.dgn		DRAWN - BK	REVISED -
	PLOT SCALE = 50.0000' / IN.	CHECKED - GFL	REVISED -
	PLOT DATE = 8/12/2011	DATE - 12/17/10	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF	SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	128R-3	LAKE	518	7
CONTRACT NO. 60953				
FED. ROAD DIST. NO. 1   ILLINOIS   FED. AID PROJECT				