

				CONSTRUCTION CODE								
				100% LAKE COUNTY								
				ROADWAY	SN-049-0199	BOX CULVERT	RETAINING WALL	TRAFFIC SIGNALS	LIGHTING URBAN	100%	100%	
				0003	BRIDGE	0040	0040	0021	0021	VILLAGE OF	IDOT	
				URBAN	0010	URBAN	URBAN	URBAN	0021	LIBERTYVILLE	0043	
					URBAN				0021	0043	0043	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY									
* 72900100	METAL POST - TYPE A	FOOT	758	758								
* 72900200	METAL POST - TYPE B	FOOT	889	889								
* 73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	20	20								
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	9.2	9.2								
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1710	1710								
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	871	871								
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	19066	19066								
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	7764	7764								
* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	2231	2231								
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	969	969								
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	539	539								
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	825	825								
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	10	10								
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	113	113								
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	400	400								
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	27	27								
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	11042	11042								
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	2						2			
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1						1			
* 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	2					2				
* 81000300	CONDUIT IN TRENCH, 1" DIA., GALVANIZED STEEL	FOOT	100						100			
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	16448					16358	90			
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	271					271				
* 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	87					87				
* 81000900	CONDUIT IN TRENCH, 3 1/2" DIA., GALVANIZED STEEL	FOOT	14					14				
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	60					60				
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	2293					2293				
* 81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	154					154				
* 81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	790						790			
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	1389					1389				
* 81200100	CONDUIT EMBEDDED IN STRUCTURE, 1" DIA., GALVANIZED STEEL	FOOT	220						220			
* 81400100	HANDHOLE	EACH	36					36				
* 81400200	HEAVY-DUTY HANDHOLE	EACH	6					6				
* 81400300	DOUBLE HANDHOLE	EACH	4					4				

\* SPECIALITY ITEM

FILE NAME =	USER NAME = IDOT	DESIGNED - EJM	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>				<b>SUMMARY OF QUANTITIES</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
11\102901\cadd sheets\sh-t-soq007.dgn		DRAWN - BK	REVISED -									330	128R-3	LAKE	518	11			
PLOT SCALE = 50.0000' / IN.		CHECKED - GFL	REVISED -									SCALE: SHEET NO. OF SHEETS STA. TO STA.				FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			
PLOT DATE = 8/12/2011		DATE - 12/17/10	REVISED -																