

				CONSTRUCTION CODE							
				100% LAKE COUNTY					100% VILLAGE OF LIBERTYVILLE	100% IDOT	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0003 URBAN	SN-049-0199 BRIDGE 0010 URBAN	BOX CULVERT 0040 URBAN	RETAINING WALL 0040 URBAN	TRAFFIC SIGNALS 0021 URBAN	LIGHTING URBAN 0021	0043	0043
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	28					28			
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	8					8			
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	13					13			
87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	117					117			
87900200	DRILL EXISTING HANDHOLE	EACH	5					5			
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	14					14			
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1					1			
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2					2			
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	5					5			
88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	5					5			
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4					4			
88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	4					4			
88102757	PEDESTRIAN SIGNAL HEAD, LED, 3-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2					2			
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	19					19			
88500100	INDUCTIVE LOOP DETECTOR	EACH	28					28			
88600100	DETECTOR LOOP, TYPE I	FOOT	66					66			
88600700	PREFORMED DETECTOR LOOP	FOOT	1766					1766			
88700200	LIGHT DETECTOR	EACH	6							6	
88700300	LIGHT DETECTOR AMPLIFIER	EACH	2							2	
88800100	PEDESTRIAN PUSH-BUTTON	EACH	20					20			
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2					2			
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	8100						8100		
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1					1			
89502380	REMOVE EXISTING HANDHOLE	EACH	17					17			
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	8					8			
X0327354	AGGREGATE SUBGRADE 12", SPECIAL	SQ YD	116970	116970							
Z0004638	PAVEMENT BREAKING	SQ YD	10000	10000							
Z0005216	HOT-MIX ASPHALT STABILIZATION 6" AT STEEL PLATE BEAM GUARD RAIL	SQ YD	1433	1433							
Z0007118	UNTREATED TIMBER LAGGING	SQ FT	5468				5468				
Z0007430	TEMPORARY SIDEWALK	SQ FT	3000	3000							
Z0013302	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	1120				1120				
Z0013797	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	1678	1678							
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1							

\* SPECIALITY ITEM

FILE NAME = H:\102901\cadd sheets\sh-t-soq809.dgn  
 USER NAME = IDOT  
 PLOT SCALE = 50.0000' / IN.  
 PLOT DATE = 8/12/2011

DESIGNED - EJM	REVISED -
DRAWN - BK	REVISED -
CHECKED - GFL	REVISED -
DATE - 12/17/10	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 330	SECTION 128R-3	COUNTY LAKE	TOTAL SHEETS 518	SHEET NO. 13
CONTRACT NO. 60953				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				