

|                     |   |                 |                | CONSTRUCTION CODE |                   |             |                |                 |                |                              |           |  |
|---------------------|---|-----------------|----------------|-------------------|-------------------|-------------|----------------|-----------------|----------------|------------------------------|-----------|--|
|                     |   |                 |                | 100% LAKE COUNTY  |                   |             |                |                 |                |                              |           |  |
| URBAN               |   |                 |                | ROADWAY           | SN-049-0199       | BOX CULVERT | RETAINING WALL | TRAFFIC SIGNALS | LIGHTING URBAN | 100%                         | 100%      |  |
| CODE NO.            | ITEM  | UNIT            | TOTAL QUANTITY | 0003 URBAN        | BRIDGE 0010 URBAN | 0040 URBAN  | 0040 URBAN     | 0021 URBAN      | 0021           | VILLAGE OF LIBERTYVILLE 0043 | IDOT 0043 |  |
| Z0018500            | DRAINAGE STRUCTURES TO BE CLEANED                                       | EACH            | 10             | 10                |                   |             |                |                 |                |                              |           |  |
| Z0022800            | FENCE REMOVAL   | FOOT            | 2700           | 2700              |                   |             |                |                 |                |                              |           |  |
| Z0026402            | FURNISHING SOLDIER PILES (HP SECTION)                                   | FOOT            | 2905           |                   |                   |             | 2905           |                 |                |                              |           |  |
| Z0026407            | TEMPORARY SHEET PILING  | SQ FT           | 3775           | 432               |                   | 1723        | 1620           |                 |                |                              |           |  |
| Z0030260            | IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3 | EACH            | 16             | 16                |                   |             |                |                 |                |                              |           |  |
| Z0030850            | TEMPORARY INFORMATION SIGNING   | SQ FT           | 1000           | 1000              |                   |             |                |                 |                |                              |           |  |
| Z0033020            | LUMINAIRE SAFETY CABLE ASSEMBLY   | EACH            | 45             |                   |                   |             |                |                 | 45             |                              |           |  |
| Z0033028            | MAINTENANCE OF LIGHTING SYSTEM  | CAL MO          | 18             |                   |                   |             |                |                 | 18             |                              |           |  |
| Z0042002            | POROUS GRANULAR EMBANKMENT, SUBGRADE                                    | CU YD           | 28780          | 23706             |                   | 1844        | 3230           |                 |                |                              |           |  |
| Z0046304            | PIPE UNDERDRAINS FOR STRUCTURES 4"                                      | FOOT            | 1553           |                   | 362               |             | 1191           |                 |                |                              |           |  |
| Z0056608            | STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH                           | FOOT            | 100            | 100               |                   |             |                |                 |                |                              |           |  |
| Z0056610            | STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH                           | FOOT            | 100            | 100               |                   |             |                |                 |                |                              |           |  |
| Z0056612            | STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH                           | FOOT            | 100            | 100               |                   |             |                |                 |                |                              |           |  |
| Z0056800            | SANITARY SEWER 6"   | FOOT            | 70             |                   |                   |             |                |                 |                | 70                           |           |  |
| Z0057100            | SANITARY SEWER 12"  | FOOT            | 466            |                   |                   |             |                |                 |                | 466                          |           |  |
| Z0062456            | TEMPORARY PAVEMENT  | SQ YD           | 5740           | 5740              |                   |             |                |                 |                |                              |           |  |
| Z0064800            | SELECTIVE CLEARING  | UNIT            | 5              | 5                 |                   |             |                |                 |                |                              |           |  |
| Z0073002            | TEMPORARY SOIL RETENTION SYSTEM   | SQ FT           | 15585          |                   | 5640              | 2345        | 7800           |                 |                |                              |           |  |
| Z0073345            | SLEEPER SLAB  | FOOT            | 401            | 401               |                   |             |                |                 |                |                              |           |  |
| Z0073510            | TEMPORARY TRAFFIC SIGNAL TIMING   | EACH            | 2              |                   |                   |             |                | 2               |                |                              |           |  |
| X0301797            | GATE REMOVAL  | EACH            | 2              | 2                 |                   |             |                |                 |                |                              |           |  |
| * X0324455          | DRILLING AND SETTING SOLDIER PILES (IN SOIL)                            | CU FT           | 4445           |                   |                   |             | 4445           |                 |                |                              |           |  |
| X0325751            | DRIVING SOLDIER PILES   | FOOT            | 1763           |                   |                   |             | 1763           |                 |                |                              |           |  |
| X0325786            | GATES TO BE REMOVED AND RE-ERECTED                                      | EACH            | 1              | 1                 |                   |             |                |                 |                |                              |           |  |
| X0326309            | RELOCATE EXISTING REMOTE-CONTROLLED VIDEO SYSTEM (SPECIAL)              | EACH            | 1              |                   |                   |             |                | 1               |                |                              |           |  |
| <del>X0326309</del> | <del>RELOCATE EXISTING REMOTE-CONTROLLED VIDEO SYSTEM (SPECIAL)</del>   | <del>EACH</del> | <del>1</del>   |                   |                   |             |                | <del>1</del>    |                |                              |           |  |
| X0326310            | RELOCATE EXISTING SWITCH (SPECIAL)                                      | EACH            | 1              |                   |                   |             |                | 1               |                |                              |           |  |
| <del>X0326310</del> | <del>RELOCATE EXISTING SWITCH (SPECIAL)</del>                           | <del>EACH</del> | <del>1</del>   |                   |                   |             |                | <del>1</del>    |                |                              |           |  |
| X0326658            | CURED-IN-PLACE PIPE LINER, 10"  | FOOT            | 1289           | 512               |                   |             |                |                 |                | 265                          | 512       |  |
| X0326713            | SANITARY SEWER CONNECTION   | EACH            | 7              |                   |                   |             |                |                 |                | 7                            | 0         |  |
| X0487800            | SANITARY SEWER REMOVAL 12"  | FOOT            | 486            |                   |                   |             |                |                 |                | 486                          | 0         |  |
| X2070304            | POROUS GRANULAR EMBANKMENT, SPECIAL                                     | CU YD           | 749            |                   | 304               |             | 445            |                 |                |                              |           |  |
| X2080250            | TRENCH BACKFILL, SPECIAL  | CU YD           | 1477           | 375               |                   |             |                |                 |                | 727                          | 375       |  |
| * X2501800          | SEEDING CLASS 4 (MODIFIED)  | ACRE            | 4.89           | 4.89              |                   |             |                |                 |                |                              |           |  |

\* SPECIALITY ITEM

|  |                              |                 |           |
|--|------------------------------|-----------------|-----------|
| FILE NAME =<br>u:\102901\cadd sheets\sh-t-soq010.dgn | USER NAME = IDOT             | DESIGNED - EJM  | REVISED - |
|  |                              | DRAWN - BK      | REVISED - |
|  | PLOT SCALE = 50.0000 ' / IN. | CHECKED - GFL   | REVISED - |
|  | PLOT DATE = 8/12/2011        | DATE - 12/17/10 | REVISED - |

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

| SUMMARY OF QUANTITIES |           |           |              |
|-----------------------|-----------|-----------|--------------|
| SCALE:                | SHEET NO. | OF SHEETS | STA. TO STA. |
|                       |           |           |              |

|   |                   |                |                     |                 |
|---|-------------------|----------------|---------------------|-----------------|
| F.A.P. RTE.<br>330                                  | SECTION<br>128R-3 | COUNTY<br>LAKE | TOTAL SHEETS<br>518 | SHEET NO.<br>14 |
| CONTRACT NO. 60953                                  |                   |                |                     |                 |
| FED. ROAD DIST. NO. 1   ILLINOIS   FED. AID PROJECT |                   |                |                     |                 |