



**SCHEDULE OF TEMPORARY INTERCONNECT QUANTITIES**

ITEM	UNIT	QTY
CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FT	65
CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FT	16
TRENCH AND BACKFILL FOR ELECTRICAL WORK	FT	65
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EA	2
SPAN WIRE	FT	3043
TEMPORARY AERIAL FIBER OPTIC CABLE, NO. 62.5/125, MM12F, SM12F	FT	3553
DRILL EXISTING HANDHOLE	EA	2
REMOVE EXISTING HANDHOLE	EA	2
TRAFFIC SIGNAL WOOD POLE, 60 FT, CLASS 4	EA	20
REMOVE EXISTING TEMPORARY TRAFFIC SIGNAL EQUIPMENT	EA	1

NOTE:  
THE TRAFFIC SIGNAL CONTROLLER EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.

RESTORATION OF WORK AREA. RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

FILE NAME = P:\11386.000 - CRA IL Rte 21\Working Files\Drawing Files\Shc\27-TMP SCH.dgn	USER NAME = IDOT - District 01	DESIGNED - TCM	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>TEMPORARY INTERCONNECT SCHEMATIC</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 100.0000000' / in.	CHECKED - TCM	REVISED -		ILL RTE 21 (MILWAUKEE AVE.) & ILL RTE 137 (BUCKLEY RD.)			330	128R-3	LAKE	518	214
	PLOT DATE = 7/27/2011	DATE - 07/08/11	REVISED		SCALE: N.T.S.	SHEET NO. 27 OF 41 SHEETS	STA. -	TO STA. -	CONTRACT NO. 60953			
ILLINOIS FED. AID PROJECT												