



SCHEDULE OF TEMPORARY INTERCONNECT QUANTITIES							
ITEM	UNIT	QTY					
CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FT	65					
CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FT	16					
TRENCH AND BACKFILL FOR ELECTRICAL WORK	FT	65					
MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EA	2					
SPAN WIRE	FT	3043					
TEMPORARY AERIAL FIBER OPTIC CABLE, NO. 62.5/125, MM12F, SM12F	FT	3553					
DRILL EXISTING HANDHOLE	EA	2					
REMOVE EXISTING HANDHOLE	EA	2					
TRAFFIC SIGNAL WOOD POLE, 60 FT, CLASS 4	EA	20					
REMOVE EXISTING TEMPORARY TRAFFIC SIGNAL EQUIPMENT	EA	1					

NOTE: THE TRAFFIC SIGNAL CONTROLLER EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM. RESTORATION OF WORK AREA. RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

FILE NAME =	USER NAME = IDOT - District 01	DESIGNED	-	ТСМ	REVISED -
P:\11306.000 - CRA IL Rte 21\Working File	s\Drawing Files\Sht\27-TMP SCM.dgn	DRAWN	-	TCM	REVISED -
	PLOT SCALE = 100.0000000 '/ in.	CHECKED	-	TCM	REVISED -
	PLOT DATE = 7/13/2011	DATE	-	07/08/11	REVISED

LIBERTYVILLE 📩 🗏

FIRE STATION

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

*					
TEMPORARY INTERCONNECT SCHEMATIC	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ILL RTE 21 (MILWAUKEE AVE.) & ILL RTE 137 (BUCKLEY RD.)	330	128R-3	LAKE	518	215
TEL IVIE 21 WILLIAMICE AVEN & TEL IVIE 151 (BOOKEE) INDI	4		CONTRACT	NO. 6	OC18
CALE: N.T.S. SHEET NO. 27 OF 41 SHEETS STA TO STA	ILLINOIS FED. AID PROJECT				