

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				80% FED 20% STATE	80% FED 20% STATE	100% ISTHA
				ROADWAY 0004 RURAL	BRIDGE 0011 S.N. 016-0199	BRIDGE 0011 S.N. 016-0199
						URBAN
50900105	ALUMINUM RAILING, TYPE L	FOOT	501		501	
51500100	NAME PLATES	EACH	1		1	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	192		192	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	56			56
52100530	ANCHOR BOLTS, 1 1/4"	EACH	112			112
52100540	ANCHOR BOLTS, 1 1/2"	EACH	4			4
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	84		84	
60608521	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.24	FOOT	96	96		
60619200	CONCRETE MEDIAN, TYPE SB-6.06	SQ FT	3,523	3,523		
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	125	125		
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2	2		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2		
63200310	GUARDRAIL REMOVAL	FOOT	296	296		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	16	16		
67100100	MOBILIZATION	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	112	112		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	24	24		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	424	424		
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	12,271	12,271		
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	616	616		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4,643	4,643		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	387.5	387.5		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	387.5	387.5		
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	3,846	3,846		
* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	1,051	1,051		
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	194	194		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	12	12		
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	16	16		
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	24	24		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	6	6		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,268	1,268		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	49	49		

- \* SPECIALTY ITEMS
- \*\* TOLLWAY ITEMS

FILE NAME = 62099CS002.dgn	USER NAME = 3204030193	DESIGNED - PK	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>ILLINOIS RTE 1 OVER TRI-STATE I-80 / I-294 SUMMARY OF QUANTITIES</b>	F.A.P. RTE. 876	SECTION 2001-001BR	COUNTY COOK	TOTAL SHEETS 62	SHEET NO. 4
PLOT SCALE = 50.000' / IN.	CHECKED - RPI	REVISED -	SCALE: NONE			SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			
PLOT DATE = 6/29/2011	DATE - 07/01/2011	REVISED -	CONTRACT NO. 62099							

Rev. 9-8-11