

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				80% FED 20% STATE	80% FED 20% STATE	100% ISTHA
				ROADWAY 0004 RURAL	BRIDGE 0011 S.N. 016-0199	BRIDGE 0011 S.N. 016-0199
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	775	775		
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	352	352		
* 81100605	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC COATED GALVANIZED STEEL	FOOT	550	550		
* 81300730	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16" X 14" X 6"	EACH	4	4		
* 81400100	HANDHOLE	EACH	10	10		
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	775	775		
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	12	12		
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	1	1		
Z0004552	APPROACH SLAB REMOVAL	SQ YD	590	590		
Z0010400	CLEANING BRIDGE SEATS	SQ FT	987			987
Z0013798	CONSTRUCTION LA YOUT	L SUM	1	1		
Z0018900	DRILL AND GROUT DOWEL BARS	EACH	882	882		
Z0021906	SILICONE JOINT SEALER, 1.5"	FOOT	66			66
Z0026346	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1		
Z0026407	TEMPORARY SHEET PILING	SQ FT	282		282	
Z0030280	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2		
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	598	598		
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	250		250	
Z0062456	TEMPORARY PAVEMENT	SQ YD	398	398		
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	220		220	
X2502014	SEEDING, CLASS 4A (MODIFIED)	ACRE	0.09	0.09		
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1		
X7240505	RELOCATE SIGN PANEL AND POST	EACH	1	1		
X7240605	REMOVE AND RE-ERECT BRIDGE MOUNTED SIGN	EACH	4		4	
X8210305	PROTECTION AND MAINTENANCE OF EXISTING UNDERPASS LIGHTING	L SUM	1	1		
X8440120	REMOVE AND RE-ERECT EXISTING LIGHTING UNIT	EACH	1	1		
** 58700300	CONCRETE SEALER	SQ FT	17,100			17,100
** 59200101	BRIDGE WASHING NO. 1	EACH	1			1
** JS121200	LOW PRESSURE EPOXY INJECTION	FOOT	53			53
** Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	57			57
** Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	55			55
** JT783005	WATERBLAST PAVEMENT MARKING REMOVAL WITH VACUUM RECOVERY	SQ FT	368	368		

- * SPECIALTY ITEMS
- ** TOLLWAY ITEMS

FILE NAME = 62099CS083.dgn	USER NAME = 3204030193	DESIGNED - PK	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ILLINOIS RTE 1 OVER TRI-STATE I-80 / I-294 SUMMARY OF QUANTITIES			F.A.P. RTE. 876	SECTION 2001-001BR	COUNTY COOK	TOTAL SHEETS 62	SHEET NO. 5
PLOT SCALE = 50.000' / IN.	CHECKED - RPI	REVISED -	SCALE: NONE					SHEET NO. OF SHEETS	STA. TO STA.	CONTRACT NO. 62099		
PLOT DATE = 6/29/2011	DATE - 07/01/2011	REVISED -	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT									