

21101615 TOPSOIL FURNISH AND PLACE, 4"					
LOCATION					AREA (SQ YD)
18+17.64	LT	TO	18+34.25	LT	7
19+03.62	RT	TO	19+84.27	RT	58
19+32.10	LT	TO	19+84.27	LT	39
22+42.93	RT	TO	22+95.10	RT	42
22+42.93	LT	TO	22+98.58	LT	46
TOTAL					192

42001300 PROTECTIVE COAT					
LOCATION					AREA (SQ YD)
BRIDGE AND BRIDGE APPROACH SLAB					3,250
BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)					103
CONCRETE MEDIAN, TYPE SB-6.06					489
COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.24					32
TOTAL					3,874

48203021 HOT-MIX ASPHALT SHOULDERS, 6"					
LOCATION					AREA (SQ YD)
19+21.21	RT	TO	19+31.21	RT	4
19+52.85	LT	TO	19+62.85	LT	1
19+84.27	RT	TO	19+98.85	RT	7
19+84.27	LT	TO	19+98.85	LT	7
22+28.25	RT	TO	22+42.93	RT	7
22+28.25	LT	TO	22+42.93	LT	6
22+64.35	RT	TO	22+74.35	RT	5
22+64.35	LT	TO	22+74.35	LT	4
TOTAL					41

70300520 PAVEMENT MARKING TAPE, TYPE III 4"				
	WHITE, SOLID (FOOT)	WHITE, SKIP-DASH (FOOT)	YELLOW, SOLID (FOOT)	SUBTOTAL
STAGE 1	1,776	124	2,532	4,432
STAGE 2	1,791	130	2,602	4,523
STAGE 3		256	3,060	3,316
TOTAL				12,271

70300550 PAVEMENT MARKING TAPE, TYPE III 8"	
	WHITE, SOLID (FOOT)
STAGE 1	276
STAGE 2	340
TOTAL	616

25000210 SEEDING, CLASS 2A					
LOCATION					AREA (ACRE)
18+17.64	LT	TO	18+34.25	LT	0.001
19+03.62	RT	TO	19+84.27	RT	0.01
19+32.10	LT	TO	19+84.27	LT	0.008
22+42.93	RT	TO	22+95.10	RT	0.009
22+42.93	LT	TO	22+98.58	LT	0.01
TOTAL					0.04

42001420 BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)					
LOCATION					AREA (SQ YD)
19+62.85	RT	TO	19+68.85	RT	25
19+62.85	LT	TO	19+68.85	LT	26
22+58.35	RT	TO	22+64.35	RT	26
22+58.35	LT	TO	22+64.35	LT	26
TOTAL					103

60608521 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.24					
LOCATION					LENGTH (FOOT)
19+21.21	RT	TO	19+68.85	RT	48
19+52.85	LT	TO	19+68.85	LT	16
22+58.35	RT	TO	22+74.35	RT	16
22+58.35	LT	TO	22+74.35	LT	16
TOTAL					96

70301000 WORK ZONE PAVEMENT MARKING REMOVAL					
	WHITE, SOLID LINE 4" (SQ FT)	WHITE, SKIP-DASH LINE 4" (SQ FT)	YELLOW, SOLID LINE 4" (SQ FT)	WHITE, SOLID LINE 8" (SQ FT)	SUBTOTAL
STAGE 1	592	41	844	184	1,661
STAGE 2	597	43	867	227	1,734
STAGE 3		85	1,020		1,105
SHORT TERM PAV. MARKINGS		141			141
TOTAL					4,643

25000400 NITROGEN FERTILIZER NUTRIENT	4 LB
25000500 PHOSPHORUS FERTILIZER NUTRIENT	4 LB
25000600 POTASSIUM NUTRIENT	4 LB
FERTILIZERS SHALL BE APPLIED AT RATE OF 90LB/ACRE	
25100630 EROSION CONTROL BLANKET	192 SQ YD

44000100 PAVEMENT REMOVAL					
LOCATION					AREA (SQ YD)
19+62.85	RT	TO	19+68.85	RT	26
19+62.85	LT	TO	19+68.85	LT	26
22+58.35	RT	TO	22+64.35	RT	24
22+58.35	LT	TO	22+64.35	LT	27
TEMPORARY PAVEMENT REMOVAL					
18+17.64	LT	TO	18+34.25	LT	7
15+30.00	CL	TO	19+68.85	CL	195
22+58.35	CL	TO	27+00.00	CL	196
TOTAL					501

60619200 CONCRETE MEDIAN, TYPE SB-6.06					
LOCATION					AREA (SQ FT)
15+30.00	TO	19+68.85			1756
22+58.35	TO	27+00.00			1767
TOTAL					3523

LOCATION		70400100 TEMPORARY CONCRETE BARRIER (FOOT)	70400200 RELOCATE TEMPORARY CONCRETE BARRIER (FOOT)
18+90.00	RT TO 22+60.00	LT 387.5	
19+50.00	RT TO 23+30.00	LT	387.5
TOTAL		387.5	387.5

28000400 PERIMETER EROSION BARRIER					
LOCATION					LENGTH (FOOT)
18+04	RT	TO	19+86	RT	245
18+08	LT	TO	19+86	LT	233
22+41	RT	TO	24+06	RT	230
22+41	LT	TO	24+06	LT	233
TOTAL					941

44000500 COMBINATION CURB AND GUTTER REMOVAL					
LOCATION					LENGTH (FOOT)
19+21.21	RT	TO	19+68.85	RT	48
19+52.85	LT	TO	19+68.85	LT	16
22+58.35	RT	TO	22+74.35	RT	16
22+58.35	LT	TO	22+74.35	LT	16
TOTAL					96

63000001 STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS					
LOCATION					LENGTH (FOOT)
19+03.62	RT	TO	19+41.12	RT	37.5
19+32.10	LT	TO	19+69.60	LT	37.5
22+57.60	RT	TO	22+95.10	RT	37.5
22+86.08	LT	TO	22+98.58	LT	12.5
TOTAL					125

POLYUREA PAVEMENT MARKING TYPE I							
LOCATION		78008210 - LINE 4"			78008240 - LINE 8"		78008250 - LINE 12"
		WHITE SOLID FOOT	WHITE SKIP-DASH FOOT	YELLOW SOLID FOOT	WHITE SOLID FOOT	WHITE SKIP-DASH FOOT	WHITE CHEVRONS FOOT
10+41.36	14' RT TO 27+00.00	14' RT	420				
18+62.67	26' RT TO 23+48.60	26' RT				121	
15+30.00	14' LT TO 31+81.21	14' LT	412				
19+11.38	26' LT TO 23+54.85	26' LT				110	
19+21.12	38' RT TO 22+74.05	38' RT	353				
19+53.01	41' LT TO 22+74.05	38' LT	321				
15+30.00	2' RT TO 27+00.00	2' RT		1170			
15+30.00	2' LT TO 27+00.00	2' LT		1170			
17+58.86	26' RT TO 18+62.67	26' RT				104	
17+99.82	44' RT TO 18+62.67	26' RT				63	
17+58.37	26' LT TO 19+11.38	26' LT				153	
18+07.41	51' LT TO 19+11.38	26' LT				105	
23+48.60	26' RT TO 24+68.09	26' RT				120	
23+48.60	26' RT TO 24+35.55	52' RT				87	
23+54.85	26' LT TO 24+80.55	26' LT				126	
23+71.30	26' LT TO 24+33.50	44' LT				62	
RAMP GORE		18+25.00	RT				39
RAMP GORE		18+60.00	LT				48
RAMP GORE		24+00.00	RT				67
RAMP GORE		24+10.00	LT				40
TOTAL			3846			1051	194

31101200 SUB-BASE GRANULAR MATERIAL, TYPE B 4"					
LOCATION					AREA (SQ YD)
BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)					
19+62.85	RT	TO	19+68.85	RT	25
19+62.85	LT	TO	19+68.85	LT	26
22+58.35	RT	TO	22+64.35	RT	26
22+58.35	LT	TO	22+64.35	LT	26
COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.24					
19+21.21	RT	TO	19+68.85	RT	16
19+52.85	LT	TO	19+68.85	LT	5
22+58.35	RT	TO	22+74.35	RT	5
22+58.35	LT	TO	22+74.35	LT	5
CONCRETE MEDIAN, TYPE SB-6.06					
15+30.00	TO	19+68.85			195
22+58.35	TO	27+00.00			196
HOT-MIX ASPHALT SHOULDERS, 6"					
19+21.21	RT	TO	19+31.21	RT	4
19+52.85	LT	TO	19+62.85	LT	1
19+84.27	RT	TO	19+98.85	RT	7
19+84.27	LT	TO	19+98.85	LT	7
22+28.25	RT	TO	22+42.93	RT	7
22+28.25	LT	TO	22+42.93	LT	6
22+64.35	RT	TO	22+74.35	RT	5
22+64.35	LT	TO	22+74.35	LT	4
TOTAL					566

44003100 MEDIAN REMOVAL					
LOCATION					AREA (SQ FT)
15+30.00	TO	19+68.85			1756
22+58.35	TO	27+00.00			1768
TOTAL					3524

LOCATION	63100085 TRAFFIC BARRIER TERMINAL, TYPE 6 (EACH)	63100070 TRAFFIC BARRIER TERMINAL, TYPE 5 (EACH)
19+41.12	RT 1	
19+69.60	LT	1
22+57.60	RT	1
22+86.08	LT	1
TOTAL	2	2

44004250 PAVED SHOULDER REMOVAL					
LOCATION					AREA (SQ YD)
19+21.21	RT	TO	19+31.26	RT	4
19+52.85	LT	TO	19+62.85	LT	2
22+58.35	RT	TO	22+74.35	RT	6
22+58.35	LT	TO	22+74.35	LT	7
TOTAL					19

63200310 GUARDRAIL REMOVAL					
LOCATION					LENGTH (FOOT)
19+03.62	RT	TO	19+85.00	RT	81
19+32.10	LT	TO	19+85.00	LT	53
22+16.00	RT	TO	22+95.10	RT	79
22+16.00	LT	TO	22+98.58	LT	83
TOTAL					296

48101500 AGGREGATE SHOULDERS, TYPE B 6"					
LOCATION					AREA (SQ YD)
19+03.62	RT	TO	19+84.27	RT	35
19+32.10	LT	TO	19+84.27	LT	18
22+42.93	RT	TO	22+95.10	RT	18
22+42.93	LT	TO	22+98.58	LT	16
TOTAL					87

70300100 SHORT TERM PAVEMENT MARKINGS					
LOCATION					LENGTH (FOOT)
10+41.36	14' RT	TO	27+00.00	14' RT	166
15+30.00	14' LT	TO	31+81.21	14' LT	165
18+62.67	26' RT	TO	23+48.60	26' RT	49
19+10.70	26' LT	TO	23+54.85	26' LT	44
TOTAL					424