

78100100 RAISED REFLECTIVE PAVEMENT MARKER				
LOCATION				EACH
18+26.00	14' LT	19+68.85	14' LT	4
19+05.00	14' RT	19+68.85	14' RT	2
22+58.35	14' LT	23+20.00	14' LT	2
22+58.35	14' RT	24+00.00	14' RT	4
TOTAL				12

78100105 RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)				
LOCATION				EACH
19+68.85	TO	22+58.35	SB	8
19+68.85	TO	22+58.35	NB	8
TOTAL				16

78100200 TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER				
LOCATION				EACH
STAGE 1				
18+26.04	17' LT	23+29.10	17' LT	12
STAGE 2				
19+04.69	17' RT	23+96.21	17' RT	12
TOTAL				24

78200410 GUARDRAIL MARKERS, TYPE A				
LOCATION				(EACH)
GUARDRAIL				
19+03.62	RT	19+41.12	RT	1
19+32.10	LT	19+69.60	LT	1
22+57.60	RT	22+95.10	RT	1
22+86.08	LT	22+98.58	LT	1
TRAFFIC BARRIER TERMINAL				
		19+41.12	RT	1
		22+86.08	LT	1
TOTAL				6

78300100 PAVEMENT MARKING REMOVAL				
DESCRIPTION	LOCATION			AREA (SQ FT)
WHITE, SKIP-DASH 4"	10+41.36	TO	31+81.21	354
YELLOW, SOLID 4"	15+30.00	TO	27+00.00	579
WHITE, SOLID 8"	17+58.86	TO	24+80.55	335
TOTAL				1,268

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL				
LOCATION				EACH
18+26.00	14' LT	TO	23+20.00	12
19+20.00	26' LT	TO	23+80.00	10
19+05.00	14' RT	TO	19+68.85	2
18+46.00	26' RT	TO	19+68.85	2
22+58.35	14' RT	TO	24+00.00	4
22+58.35	26' RT	TO	23+58.26	2
TEMPORARY				
STAGE 1				
18+26.04	17' LT	TO	19+68.85	3
2258.35	17' LT	TO	23+20.10	2
STAGE 2				
19+04.69	17' RT	TO	23+96.21	12
TOTAL				49

LOCATION				81000600 CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL (FOOT)	81900200 TRENCH AND BACKFILL FOR ELECTRICAL WORK (FOOT)	
18+20	87' LT	TO	19+90	47' LT	200	200
18+20	90' LT	TO	19+95	47' LT	210	210
22+35	47' LT	TO	22+70	48' LT	50	50
22+40	47' LT	TO	22+70	71' LT	45	45
22+70	48' LT	TO	24+00	85' LT	135	135
22+70	51' LT	TO	24+00	88' LT	135	135
TOTAL				775	775	

LOCATION				81018500 CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL (FOOT)	81100605 CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC COATED GALVANIZED STEEL (FOOT)	
17+60	52' LT	TO	18+20	87' LT	70	
17+60	55' LT	TO	18+20	90' LT	70	
19+90	47' LT	TO	22+40	47' LT		280
19+95	47' LT	TO	22+35	47' LT		270
24+00	85' LT	TO	25+00	45' LT	106	
24+00	88' LT	TO	25+00	48' LT	106	
TOTAL				352	550	

LOCATION			81300730 JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 16" X 14" X 6" EACH	81400100 HANDHOLE EACH
17+60	52' LT		1	1
17+60	55' LT		1	1
18+20	87' LT		1	1
18+20	90' LT		1	1
19+90	47' LT		1	
19+95	47' LT		1	
22+35	47' LT		1	
22+40	47' LT		1	
22+70	48' LT			1
22+70	51' LT			1
24+00	85' LT			1
24+00	88' LT			1
25+00	45' LT			1
25+00	48' LT			1
TOTAL			4	10

LOCATION		83600200 LIGHT POLE FOUNDATION, 24" DIAMETER FOOT	84200804 REMOVAL OF POLE FOUNDATION EACH	X8440120 REMOVE AND RE-ERECT EXISTING LIGHTING UNIT EACH
22+60.00	RT	12	1	1
TOTAL		12	1	1

LOCATION				20062456 TEMPORARY PAVEMENT (SQ YD)	40300100 BITUMINOUS MATERIALS (PRIME COAT) (GALLON)	
18+17.64	LT	TO	18+34.25	LT	7	0.3
15+30.00	CL	TO	19+68.85	CL	195	7.8
22+58.35	CL	TO	27+00.00	CL	196	7.8
TOTAL				398	16.0	

Z0004552 APPROACH SLAB REMOVAL			AREA (SQ YD)
19+68.85	TO	19+98.85	295
22+28.35	TO	22+58.35	295
TOTAL			590

Z0018900 DRILL AND GROUT DOWEL BARS			EACH
15+30.00	TO	19+68.85	440
22+58.35	TO	27+00.00	442
TOTAL			882

LOCATION	Z0030260 IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3 (EACH)	Z0030330 IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3 (EACH)
18+90.00	RT	1
22+60.00	LT	1
19+50.00	RT	1
23+30.00	LT	1
TOTAL		2

Z0030850 TEMPORARY INFORMATION SIGNING			AREA (SQ FT)
STAGE 1			
22+50.00	RT		182
22+66.00	RT		136
STAGE 2			
19+50.00	LT		136
19+66.00	LT		144
TOTAL			598

LOCATION				Z0062456 TEMPORARY PAVEMENT (SQ YD)	40600100 BITUMINOUS MATERIALS (PRIME COAT) (GALLON)	
18+17.64	LT	TO	18+34.25	LT	7	0.3
15+30.00	CL	TO	19+68.85	CL	195	7.8
22+58.35	CL	TO	27+00.00	CL	196	7.8
TOTAL				398	16.0	

X7240505 RELOCATE SIGN PANEL AND POST			EACH
22+49.00	LT		1
TOTAL			1

X7240605 REMOVE AND RE-ERECT BRIDGE MOUNTED SIGN				EACH
20+15.00	47'	LT		1
20+40.00	47'	LT		1
22+00.00	47'	RT		1
22+25.00	47'	RT		1
TOTAL				4

J7783005 WATERBLAST PAVEMENT MARKING REMOVAL WITH VACUUM RECOVERY				
DESCRIPTION	LOCATION			AREA (SQ FT)
WHITE, SOLID 8"	17+99.82	TO	24+35.55	181
WHITE, SOLID 12"	17+99.82	TO	24+36.98	187
TOTAL				368