


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE
				ROADWAY 0004	BRIDGE 0014	LANDSCAPE 0031	TRAINEES 0042
				URBAN	URBAN	URBAN	URBAN
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	90	90			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	60	60			
20200100	EARTH EXCAVATION	CU YD	200	200			
20800150	TRENCH BACKFILL	CU YD	126	126			
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	160	160			
25000312	SEEDING, CLASS 4A	ACRE	0.25	0.25			
25000110	SEEDING, CLASS 1A	ACRE	0.25	0.25			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3	3			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3	3			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3	3			
25100115	MULCH, METHOD 2	ACRE	0.25	0.25			
25100630	EROSION CONTROL BLANKET	SQ YD	341	341			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	9	9			
28000400	PERIMETER EROSION BARRIER	FOOT	674	674			
28000510	INLET FILTERS	EACH	10	10			
28100109	STONE RIPRAP, CLASS A5	SQ YD	314		314		
28200200	FILTER FABRIC	SQ YD	314		314		
35101600	AGGREGATE BASE COURSE, TYPE B, 4"	SQ YD	673	673			
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	327	327			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	452	452			
44003100	MEDIAN REMOVAL	SQ FT	1371	1371			
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1		
50102400	CONCRETE REMOVAL	CU YD	36		36		
50200100	STRUCTURE EXCAVATION	CU YD	98		98		
50300100	FLOOR DRAINS	EACH	4		4		
50300225	CONCRETE STRUCTURES	CU YD	60		60		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	660		660		
50300260	BRIDGE DECK GROOVING	SQ YD	1,104		1,104		
50300300	PROTECTIVE COAT	SQ YD	1,311		1,311		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	187,230		187,230		
50800515	BAR SPLICERS	EACH	84		84		
51500100	NAME PLATES	EACH	1		1		
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	142	142			
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	65		65		
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1			
60240210	INLETS, TYPE B, TYPE 1 FRAME, OPEN LID	EACH	3	3			
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1			

• DENOTES SPECIAL PROVISION

FILE NAME = ...Roadway\DI-62101-sht-5001.dgn	DESIGNED - MC	REVISED -	 600 W FULTON ST CHICAGO, ILLINOIS 60611-1209 TEL: 312 464 9100 FAX: 312 558 1217 WEB: www.sepstein.com	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION			SUMMARY OF QUANTITIES				F.A.U. RTE. 1257	SECTION 104RB-R	COUNTY LAKE	TOTAL SHEETS 54	SHEET NO. 3
PLOT TIME = 5:17:42 PM	DRAWN - MC	REVISED -					SCALE: N/A	SHEET NO. 1 OF 3 SHEETS	STA.	TO STA.	CONTRACT NO. 62102				
PLOT DATE = 6/23/2011	CHECKED - TRP	REVISED -					ILLINOIS FED. AID PROJECT								

Rev.