

CONSTRUCTION TYPE CODES

NEW BRIDGE: SN 016-6078

CODE NO.	ITEM	UNIT	QUANTITY	0021	0008
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	550	550	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	214	214	
20101000	TEMPORARY FENCE	FOOT	2700	2700	
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	23	23	
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	45	45	
20200100	EARTH EXCAVATION	CU YD	2126	2126	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	100	100	
20400800	FURNISHED EXCAVATION	CU YD	773	773	
20800150	TRENCH BACKFILL	CU YD	47	47	
* 21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	6553	6553	
21400100	GRADING AND SHAPING DITCHES	FOOT	100	100	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	77	77	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	77	77	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	77	77	
* 25200110	SODDING, SALT TOLERANT	SQ YD	6553	6553	
* 25200200	SUPPLEMENTAL WATERING	UNIT	18	18	
28000500	INLET AND PIPE PROTECTION	EACH	10	10	
28000510	INLET FILTERS	EACH	3	3	
28100107	STONE RIPRAP, CLASS A4	SQ YD	59	59	
28200200	FILTER FABRIC	SQ YD	59	59	
31101100	SUB BASE GRANULAR MATERIAL, TYPE B	CU YD	100	100	
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	960	960	
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	4107	4107	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	616	616	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	474	474	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	8640	8640	
42400800	DETECTABLE WARNINGS	SQ FT	282	282	
44000100	PAVEMENT REMOVAL	SQ YD	44	44	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	375	375	
44000600	SIDEWALK REMOVAL	SQ FT	700	700	
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	182	182	
542A5491	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36"	FOOT	48	48	
54214731	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 36"	EACH	2	2	
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	4	4	
54248160	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 36"	EACH	2	2	
60107700	PIPE UNDERDRAINS 6"	FOOT	15	15	
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
60255500	MANHOLES TO BE ADJUSTED	EACH	8	8	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1	
60603900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (ABUTTING EXISTING PAVEMENT)	FOOT	233	233	
60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	FOOT	180	180	
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	20	20	
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1	
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1	
67100100	MOBILIZATION	L SUM	1	1	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
72000100	SIGN PANEL - TYPE 1	SQ FT	55	55	
72900100	METAL POST - TYPE A	FOOT	161	161	
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2	2	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1877	1877	
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	2750	2750	

* - SPECIALTY ITEM

FILE NAME = DETAILSH.DWG	DESIGNED --	REVISED --		VILLAGE OF HOFFMAN ESTATES 1900 Hassell Road, Hoffman Estates, IL 60169 Phone Number: 847 252-5800	Higgins Road Bicycle and Pedestrian Project			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN --	REVISED --			Summary of Quantities			341	08-00080-00-BT	Cook	86	3
	CHECKED --	REVISED --			SCALE: NONE	SHEET NO. 1 OF 2 SHEETS	STA.	TO STA.	CONTRACT NO. 63233			
	DATE --	REVISED --			ILLINOIS FED. AID PROJECT CMM 9003(243)							