

PLAN	SURVEYED	DATE
	PLOTTED	BY
	CHECKED	
	REVIEWED	
	FILED	
	FILE NAME	
	NO.	

PROFILE	SURVEYED	DATE
	PLOTTED	BY
	CHECKED	
	REVIEWED	
	FILED	
	FILE NAME	
	NO.	

SUMMARY OF QUANTITIES					ROADWAY	LIGHTING	TRAFFIC SIGNALS			NON-PART
CODE NO.	PAY ITEM	UNIT	QUANTITY	70% FED 30% LA	70% FED 30% LA	YORK STREET & IL RTE 38 RAMPS	INTERCONNECT	EMERGENCY VEHICLE PREEMPTION	100% ELMHURST	100% ELMHURST
				0004	0021		0021		0021	0043
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	6	6						
20101100	TREE TRUNK PROTECTION	EACH	11	11						
20101200	TREE ROOT PRUNING	EACH	11	11						
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	11	11						
20200100	EARTH EXCAVATION	CU YD	2,723	2,723						
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,017	1,017						
20400800	FURNISHED EXCAVATION	CU YD	50	50						
20800150	TRENCH BACKFILL	CU YD	862	862						
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SO YD	264	264						
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	7,544	7,544						
25000210	SEEDING, CLASS 2A	ACRE	1.50	1.50						
25000312	SEEDING, CLASS 4A	ACRE	0.25	0.25						
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	158	158						
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	158	158						
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	158	158						
25100630	EROSION CONTROL BLANKET	SO YD	7,544	7,544						
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	175	175						
28000305	TEMPORARY DITCH CHECKS	FOOT	91	91						
28000510	INLET FILTERS	EACH	13	13						
35101700	AGGREGATE BASE COURSE, TYPE B 5"	SO YD	71	71						
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SO YD	1,202	1,202						
35300600	PORTLAND CEMENT CONCRETE BASE COURSE 11"	SO YD	142	142						
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,014	1,014						
40600300	AGGREGATE (PRIME COAT)	TON	2	2						
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	650	650						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	75	75						
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	8	8						
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	826	826						
40701961	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14"	SO YD	673	673						
42000521	PORTLAND CEMENT CONCRETE PAVEMENT 11" (JOINTED)	SO YD	1,022	1,022						
42001110	HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 11"	SO YD	113	113						
42001300	PROTECTIVE COAT	SO YD	1,977	1,977						
44000100	PAVEMENT REMOVAL	SO YD	1,331	1,331						
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,968	1,968						
44000600	SIDEWALK REMOVAL	SO FT	682	682						
44003100	MEDIAN REMOVAL	SO FT	301	301						

- SPECIALTY ITEM
- CONSTRUCTION TYPE CODE = 0042

FILE NAME =	USER NAME = jmgolemba	DESIGNED - ESN	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	YORK STREET AT IL RTE 38 RAMPS/BRUSH HILL ROAD SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
gr\ch08\0807\road\phase 2\sheets\DX0807	SumQty.dgn	DRAWN - AJP	REVISED -			2678	09-00171-00-CH	DUPAGE	85	3
PLOT SCALE = 50.000' / IN.		CHECKED - JMG	REVISED -			SCALE: NOT TO SCALE SHEET NO. 3 OF 85 SHEETS			CONTRACT NO. 63610	
PLOT DATE = 8/4/2011		DATE - 7/4/2011	REVISED -			FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT				