

PLAN	SURVEYED	DATE
NOTE BOOK	PLOTTED	
NO.	BY	
	CHECKED	
	AT	
	OF	
	WAY	
	CHECKED	
	NO.	
	CADD	
	FILE	
	NAME	

PROFILE	SURVEYED	DATE
NOTE BOOK	PLOTTED	
NO.	BY	
	CHECKED	
	AT	
	OF	
	WAY	
	CHECKED	
	NO.	
	STRUCTURE	
	NOTATION	
	CHKD	

SUMMARY OF QUANTITIES				ROADWAY	LIGHTING	TRAFFIC SIGNALS			NON-PART	
CODE NO.	PAY ITEM	UNIT	QUANTITY	70% FED 30% LA 0004	70% FED 30% LA 0021	YORK STREET & IL RTE 38 RAMPS 70% FED 30% LA	INTERCONNECT 70% FED 30% LA	EMERGENCY VEHICLE PREEMPTION 100% ELMHURST	100% ELMHURST	100% ELMHURST
							0021	0021		0043
44004250	PAVED SHOULDER REMOVAL	SO YD	1,523	1,523						
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SO YD	8	8						
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	145	145						
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	4,271	4,271						
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	1,114	1,114						
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1						
54215553	METAL END SECTIONS 18"	EACH	2	2						
5422C018	PIPE CULVERTS, CLASS C, TYPE 2 18" (TEMPORARY)	FOOT	59	59						
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	262	262						
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	80	80						
550A0640	STORM SEWERS, CLASS A, TYPE 3 12"	FOOT	407	407						
550A0770	STORM SEWERS, CLASS A, TYPE 3 42"	FOOT	4	4						
550A0780	STORM SEWERS, CLASS A, TYPE 3 48"	FOOT	271	271						
55100500	STORM SEWER REMOVAL 12"	FOOT	18	18						
55101800	STORM SEWER REMOVAL 42"	FOOT	296	296						
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	3	3						
60107600	PIPE UNDERDRAINS 4"	FOOT	1,813	1,813						
60201330	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	3	3						
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	2	2						
60208230	CATCH BASINS, TYPE C, TYPE 23 FRAME AND GRATE	EACH	3	3						
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	8	8						
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3						
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	3	3						
60237460	INLETS, TYPE A, TYPE 23 FRAME AND GRATE	EACH	1	1						
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	1	1						
60250200	CATCH BASINS TO BE ADJUSTED	EACH	1	1						
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1						
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1	1						
60500040	REMOVING MANHOLES	EACH	1	1						
60500050	REMOVING CATCH BASINS	EACH	1	1						
60500205	FILLING CATCH BASINS	EACH	3	3						
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	1,029	1,029						
60620000	CONCRETE MEDIAN, TYPE SB-6.24	SO FT	4,114	4,114						
60624600	CORRUGATED MEDIAN	SO FT	1,322	1,322						
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	3,310	3,310						
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1						

- SPECIALTY ITEM
- CONSTRUCTION TYPE CODE = 0042

FILE NAME = g:\ch08\0007\road\phase 2\sheet\DI12007	USER NAME = jingo\emba Sum0ty.dgn	DESIGNED - ESN	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	YORK STREET AT IL RTE 38 RAMPS/BRUSH HILL ROAD SUMMARY OF QUANTITIES	F.A.U. RTE. 2678	SECTION 09-00171-00-CH	COUNTY	TOTAL SHEETS 85	SHEET NO. 4
PLOT SCALE = 50.000' / 1"	CHECKED - JMC	REVISED -	SCALE: NOT TO SCALE SHEET NO. 4 OF 85 SHEETS			CONTRACT NO. 63610				
PLOT DATE = 8/4/2011	DATE - 7/4/2011	REVISED -	FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT							