

PLAN	SURVEYED	DATE
	PLOTTED	BY
	NOTED	
	RECHECKED	
	BY	
	DATE	
	NO. OF WAYS CHECKED	
	CAD FILE NAME	

PROFILE	SURVEYED	DATE
	PLOTTED	BY
	NOTED	
	RECHECKED	
	BY	
	DATE	
	STRUCTURE NOTATIONS CHECKED	

SUMMARY OF QUANTITIES				ROADWAY	LIGHTING	TRAFFIC SIGNALS			NON-PART	
CODE NO.	PAY ITEM	UNIT	QUANTITY	70% FED 30% LA	70% FED 30% LA	YORK STREET & IL RTE 38 RAMPS	INTERCONNECT	EMERGENCY VEHICLE PREEMPTION	100% ELMHURST	100% ELMHURST
				0004	0021		0021		0021	0043
66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12						
67100100	MOBILIZATION	L SUM	1	1						
70300100	SHORT TERM PAVEMENT MARKING	FOOT	4,757	4,757						
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	1,560	1,560						
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	38,073	38,073						
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5,385	5,385						
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	891	891						
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	4,374	4,374						
70400100	TEMPORARY CONCRETE BARRIER	FOOT	88	88						
72000100	SIGN PANEL - TYPE 1	SO FT	158	142		16				
72000200	SIGN PANEL - TYPE 2	SO FT	20			20				
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	2	2						
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	2	2						
72400310	REMOVE SIGN PANEL - TYPE 1	SO FT	37	37						
72900100	METAL POST - TYPE A	FOOT	143	143						
72900200	METAL POST - TYPE B	FOOT	12	12						
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	1	1						
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	1	1						
78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	423	423						
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	5,688	5,688						
78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	2,252	2,252						
78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	275	275						
78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	184	184						
78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SO FT	110	110						
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	3,599	3,599						
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	383	383						
78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	107	107						
78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	16	16						
78300100	PAVEMENT MARKING REMOVAL	SO FT	2,288	2,288						
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	25	25						
80500010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	1			1				
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	1,266			949	317			
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	479			479				
81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	52			52				
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	20			20				

• SPECIALTY ITEM  
 •• CONSTRUCTION TYPE CODE = 0042

FILE NAME = g:\ch08\0807\road\phase 2\sheets\DX0007  
 USER NAME = jngolemba  
 Sum05.dgn  
 PLOT SCALE = 58.000' / IN.  
 PLOT DATE = 8/4/2011

DESIGNED - ESN  
 DRAWN - AJP  
 CHECKED - JMG  
 DATE - 7/4/2011

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

YORK STREET AT IL RTE 38 RAMPS/BRUSH HILL ROAD  
 SUMMARY OF QUANTITIES

SCALE: NOT TO SCALE SHEET NO. 5 OF 85 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2678	09-00171-00-CH		85	5
CONTRACT NO. 63610				
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT				