

PLAN	DESIGNED	BY	DATE
NOTE BOOK	PLOTTED		
NO.	CHECKED		
	BY		
	DATE		
	FILE NAME		

PROFILE	DESIGNED	BY	DATE
NOTE BOOK	PLOTTED		
NO.	CHECKED		
	BY		
	DATE		
	FILE NAME		

SUMMARY OF QUANTITIES				ROADWAY	LIGHTING	TRAFFIC SIGNALS			NON-PART		
CODE NO.	PAY ITEM	UNIT	QUANTITY			70% FED 30% LA	70% FED 30% LA	YORK STREET & IL RTE 38 RAMPS	INTERCONNECT	EMERGENCY VEHICLE PREEMPTION	100% ELMHURST
				0004	0021	70% FED 30% LA	70% FED 30% LA	100% ELMHURST	100% ELMHURST		
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	183			183					
81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	455		455						
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	563			563					
81400100	HANDHOLE	EACH	5			5					
81400200	HEAVY-DUTY HANDHOLE	EACH	6			6					
81400300	DOUBLE HANDHOLE	EACH	2			2					
81603150	UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.6 GROUND, (EPR-TYPE RHW), 1" DIA. POLYETHYLENE	FOOT	2,176		2,176						
81603210	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (EPR-TYPE RHW), 1 1/4" DIA. POLYETHYLENE	FOOT	184		184						
81800200	AERIAL CABLE, 2-1/C NO. 4 WITH MESSENGER WIRE	FOOT	1,500		1,500						
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	3,515		1,713	1,485	317				
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	90		90						
83800505	BREAKAWAY DEVICE, COUPLING WITH ALUMINUM SKIRT	EACH	5		5						
84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	6		6						
84200804	REMOVAL OF POLE FOUNDATION	EACH	7		7						
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	6		6						
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1				1				
86200120	UNINTERRUPTIBLE POWER SUPPLY	EACH	1			1					
86400100	TRANSCEIVER - FIBER OPTIC	EACH	1				1				
87100020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	1,328				1,328				
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 IC	FOOT	1,304				1,304				
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,131					1,131			
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2,108			2,108					
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2,363			2,363					
87301295	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 20 3C	FOOT	1,131					1,131			
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	3,227			3,227					
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	443			443					
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	1,519			1,519					
87501000	TRAFFIC SIGNAL POST, 14 FT.	EACH	1			1					
87501400	TRAFFIC SIGNAL POST, 18 FT.	EACH	1			1					
87702990	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 54 FT.	EACH	1			1					
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12			12					
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4			4					
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	61			61					
87900200	DRILL EXISTING HANDHOLE	EACH	1				1				
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	8			8					
88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2			2					

- SPECIALTY ITEM
- CONSTRUCTION TYPE CODE = 0042

FILE NAME =	USER NAME = jmgolemba	DESIGNED - ESN	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	YORK STREET AT IL RTE 38 RAMPS/BRUSH HILL ROAD SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
gr\CH08\0007\Road\Phase 2\Sheets\U1X0007	SumQty.dgn	DRAWN - AJP	REVISED -			2678	09-00171-00-CH	DUPAGE	85	6
PLOT SCALE = 50.000 / / IN.	CHECKED - JMG	REVISED -	REVISED -			CONTRACT NO. 63610				
PLOT DATE = 8/22/2011	DATE - 7/4/2011	REVISED -	REVISED -	SCALE: NOT TO SCALE SHEET NO. 6 OF 85 SHEETS		FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT				