SUMMARY OF QUANTITIES				ROADWAY	LIGHTING	TRAFFIC SIGNALS			NON-PART
						YORK STREET & IL RTE 38 RAMPS	INTERCONNECT	EMERGENCY VEHICLE PREMEMPTION	
CODE NO.	PAY ITEM	UNIT	QUANTITY	70% FED 30% LA	70% FED 30% LA	70% FED 30% LA	70% FED 30% LA	100% ELMHURST	100% ELMHURST
				0004	0021	0021		0021	0043
• 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	8			8			
• 88030220	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1			1			
• 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	16			16			
• 88500100	INDUCTIVE LOOP DETECTOR	EACH	12			12			
• 88600100	DETECTOR LOOP, TYPE I	FOOT	1,061			1,061			
• 88700200	LIGHT DETECTOR	EACH	3					3	
• 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1					1	
• 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1			1			
• 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1			1			
• 89502380	REMOVE EXISTING HANDHOLE	EACH	12			10	2		
• 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	8			8			
• D2001772	EVERGREEN, PICEA ABIES (NORWAY SPRUCE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	1	1					
• K0029634	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	1	1					
X0322915	METAL LIGHT POLE, INSTALL ONLY	EACH	3		3				
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	8,215	8,215					
X4403800	MEDIAN SURFACE REMOVAL	SQ FT	3,963	3,963					
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	86						86
X6020096	MANHOLES, TYPE A, 6'-DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1	1					
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1					
• X7030025	WET REFLECTIVE TEMPORARY TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	250	250					
• X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	27,777	27,777					
• X7030040	WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 INCH	FOOT	777	777					
• X7030050	WET REFLECTIVE TEMPORARY TAPE TYPE III, 12 INCH	FOOT	360	360					
• X7830068	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS, NUMBERS AND SYMBOLS	SQ FT	423						423
• X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	5,688						5,688
• X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	2,252						2,252
• X7830078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	FOOT	275						275
• X7830090	GROOVING FOR RECESSED PAVEMENT MARKING 25"	FOOT	184						184
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	3,992	3,992					
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	2						2
Z0023204	SEDIMENT CONTROL, SILT FENCE	FOOT	2,661	2,661					
Z0030251	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1					
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	77	77					
• Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	12		12				
• Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1				1		

• SPECIALTY ITEM
•• CONSTRUCTION TYPE CODE = 0042

PLAN — SURVEYED / PLOTTED / ALIGNMENT CHECKED / BY / PLAN CHECKED / NOTE BOOK NO. / PROJECT FILE NAME / BY / DATE

PROFILE — SURVEYED / PLOTTED / GRADES CHECKED / BY / STRUCTURE NOTATIONS CHKD / NOTE BOOK NO. / BY / DATE

FILE NAME = p:\CH08\2007\Road\Phase 2\Sheets\DIX0007SumQty.dgn	USER NAME = jmgolomba	DESIGNED - ESN	REVISED -
		DRAWN - AJP	REVISED -
	PLOT SCALE = 50.000 ' / IN.	CHECKED - JMG	REVISED -
	PLOT DATE = 8/8/2011	DATE - 7/4/2011	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

YORK STREET AT IL RTE 38 RAMPS/BRUSH HILL ROAD
SUMMARY OF QUANTITIES

SCALE: NOT TO SCALE | SHEET NO. 7 OF 85 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2678	09-00171-00-CH	DUPAGE	85	7
		CONTRACT NO. 63610		
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT		