SCALE IN FEET
10  0  10  20  30  40  50

MATCH LINE A

MATCH LINE A

BROADWAY AVENUE (ILLINOIS ROUTE 25)

EXISTING R.O.W.

250' TO EXIST. DETECTION ZONE

80'

EXISTING R.O.W.

16'
2'          2'
80'
EXISTING R.O.W.
250' TO EXIST. STOP BAR
EXISTING R.O.W.
9' PARKING
10'  10'  10'  10'
9' PARKING

MATCH LINE A

MATCH LINE B

80'

250' TO STOP BAR

BENTON STREET

(9'-E-2½")
(16'-E-2½")
(23'-E-2½")
(52'-E-4")
(79'-E-4")
(69'-E-4")
(104'-E-2")
(98'-E-2")
(8'-E-2½")
(6'-E(2)-4")
(10'-E-2½")

ONLY
13'
13'
13'
13'
13'
36'
15'
66'
3.5'
66'

12'  10'  6'  10'  12'

18'
2'          2'

EXISTING R.O.W.
250' TO EXIST. DETECTION ZONE
EXISTING R.O.W.
80'

MATCH LINE B

NOTES:
1. THE VIDEO DETECTION ZONES SHALL BE REDRAWN AS SHOWN.
   THE COST OF THIS WORK SHALL BE INCLUDED IN THE COST OF
   TEMPORARY TRAFFIC SIGNAL INSTALLATION.

2. EXISTING TRAFFIC SIGNAL PHASING FOR BOTH INTERSECTIONS OF IL
   ROUTE 25 AND IL ROUTE 31 AT BENTON STREET WILL BE TEMPORARILY
   PHASED TO DETOUR TRAFFIC AWAY FROM THE BRIDGE CONSTRUCTION
   ON DOWNER PLACE. NORMAL TRAFFIC PATTERNS WILL RESUME WHEN
   THE BRIDGE CONSTRUCTION IS COMPLETE.

RESTORATION OF WORK AREA:
RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE
INCLUDED WITH THE RELATED PAY ITEM SUCH AS FOUNDATION,
CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA
COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH
AS SHOULDERS, MEDIANS, SIDEWALKS, PAVEMENT, ETC. SHALL BE
REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE
REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED
FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD
SPECIFICATIONS 252 AND 250 RESPECTIVELY.

| USER NAME = whood | DESIGNED - MJF | REVISED - 09/12/11 M.J.F. |
| FILE NAME = 860472-tsig02a.dgn | DRAWN - JMR | REVISED |
| PLOT SCALE = | CHECKED - APS | REVISED |
| PLOT DATE - 9/13/2011 | DATE - 9/13/11 | REVISED |

CITY OF AURORA

TEMPORARY TRAFFIC SIGNAL INSTALLATION PLAN
BENTON ST. AND BROADWAY AVE. (IL RT. 25)

SCALE:   SHEET NO.  1 OF  2 SHEETS   STA.          TO STA.

| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| | 07-00264-00-BR | KANE | 164 | 30 |

CONTRACT NO. 63620

FED. ROAD DIST. NO.   ILLINOIS FED. AID PROJECT