

SUMMARY OF QUANTITIES				URBAN	CONSTRUCTION TYPE CODE
CODE NUMBER	PAY ITEMS	UNITS	TOTAL QUANTITY	0014	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	680	680	
20800150	TRENCH BACKFILL	CU YD	419	419	
21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	100	100	
28000510	INLET FILTERS	EACH	19	19	
28100109	STONE RIPRAP, CLASS A5	SQ YD	415	415	
28200200	FILTER FABRIC	SQ YD	2180	2180	
31101100	SUBBASE GRANULAR MATERIAL, TYPE B	CU YD	24	24	
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1225	1225	
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	370	370	
31102712	SUBBASE GRANULAR MATERIAL, TYPE C 12"	SQ YD	72	72	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	35	35	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	970	970	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	205	205	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	100	100	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	305	305	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	1220	1220	
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	1340	1340	
42400800	DETECTABLE WARNINGS	SQ FT	36	36	
44000100	PAVEMENT REMOVAL	SQ YD	1585	1585	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	3600	3600	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	875	875	
44000600	SIDEWALK REMOVAL	SQ FT	2974	2974	
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	27	27	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	36	36	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	54	54	
44201771	CLASS D PATCHES, TYPE IIII, 10 INCH	SQ YD	63	63	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1	
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1	
50102400	CONCRETE REMOVAL	CU YD	390.7	390.7	
50200100	STRUCTURE EXCAVATION	CU YD	660.6	660.6	
50200300	COFFERDAM EXCAVATION	CU YD	686.7	686.7	
50202901	COFFERDAM (LOCATION - 1)	EACH	1	1	
50202902	COFFERDAM (LOCATION - 2)	EACH	1	1	
50202903	COFFERDAM (LOCATION - 3)	EACH	1	1	
50202904	COFFERDAM (LOCATION - 4)	EACH	1	1	
50202905	COFFERDAM (LOCATION - 5)	EACH	1	1	
50202906	COFFERDAM (LOCATION - 6)	EACH	1	1	
50300225	CONCRETE STRUCTURES	CU YD	2150.4	2150.4	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	634.2	634.2	
50300260	BRIDGE DECK GROOVING	SQ YD	1774	1774	

SUMMARY OF QUANTITIES				URBAN	CONSTRUCTION TYPE CODE
CODE NUMBER	PAY ITEMS	UNITS	TOTAL QUANTITY	0014	
50300300	PROTECTIVE COAT	SQ YD	2690	2690	
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	15122	15122	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUNDS	2300	2300	
50800105	REINFORCEMENT BARS	POUNDS	5220	5220	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUNDS	234560	234560	
50800515	BAR SPLICERS	EACH	1406	1406	
51500100	NAME PLATES	EACH	2	2	
* 56100900	WATER MAIN 12"	FOOT	175	175	
* 56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	3	3	
58700300	CONCRETE SEALER	SQ FT	1212	1212	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	261	261	
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	450	450	
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	14	14	
60265900	VALVE VAULTS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	8	8	
60266600	VALVE BOXES TO BE ADJUSTED	EACH	21	21	
60500040	REMOVING MANHOLES	EACH	2	2	
60500105	FILLING MANHOLES	EACH	1	1	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B - 6.12	FOOT	720	720	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12	
67100100	MOBILIZATION	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	20	20	
* 70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	326	326	
* 70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	3903	3903	
* 70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	191	191	
* 70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	103	103	
* 70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1959	1959	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	677	677	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	371	371	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	903	903	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2398	2398	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2541	2541	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	332	332	
* 78004110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE C - LINE 4"	FOOT	561	561	
* 78004130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE C - LINE 6"	FOOT	55	55	
* 78004150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE C - LINE 12"	FOOT	60	60	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1022	1022	
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	550	550	
* 81001100	CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL	FOOT	480	480	
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	435	435	

COMPANY NAME: HRGREEN
 PROJECT CONTACT: Michael G. Harshy
 DATE PLOTTED: 7/26/2011 10:55:38 AM
 FILE NAME: 86090472-Soq.dgn
 PLOT DRIVER: dxfplot
 PEN TABLE: Struct_22x34.tbl



USER NAME = whood
 FILE NAME = 86090472-Soq.dgn
 PLOT SCALE =
 PLOT DATE = 7/26/2011

DESIGNED - JPG
 DRAWN - WJH
 CHECKED - MGH
 DATE - 7/26/11

REVISED -
 REVISED -
 REVISED -
 REVISED -

CITY OF AURORA

SUMMARY OF QUANTITIES
DOWNER PLACE

SCALE: SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	07-00264-00-BR	KANE	164	4
CONTRACT NO. 63620			FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT	