



WATER MAIN TAGS	
100 29 LF WATER MAIN 12" STA ±108+69.90 OFFSET 8.04 LT TO 108+84.01 OFFSET 29.33 LT	103 12" VALVES IN VALVE VAULT, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID STA. 111+00 OFFSET ±2.44 RIM 657.45
101 169 LF WATER MAIN ATTACHED TO STRUCTURE 12" (INSULATED) STA 108+84.01 OFFSET 29.33 LT TO 110+52.85 OFFSET 29.33 LT	104 NOT USED
102 58 LF WATER MAIN 12" STA 110+52.85 OFFSET 29.33 LT TO ±111+00 OFFSET ±2.44 LT	

SANITARY SEWER TAGS	
200 MANHOLE, SANITARY, 5' DIAMETER, TYPE 1 FRAME CLOSED LID STA. 107+65 OFFSET 12.29 RT RIM 642.69, E. INVERT 630.16	
201 76.3 LF SANITARY SEWER 8" (SDR 26) @ 1.0%	
202 MANHOLE, SANITARY, 5' DIAMETER, TYPE 1 FRAME CLOSED LID STA. 108+41.06 OFFSET 9.59 RT RIM 641.74, W. INVERT 629.40, N. INVERT 627.41	
203 45.5 LF SANITARY SEWER 8" (SDR 26) @ 1.0%	
204 EXISTING SANITARY MANHOLE STA. 108+47.31 OFFSET 39.95 LT N. INVERT 625.16, E. INVERT 625.16, S. INVERT 626.95 (CORED AND BOOTED, COST INCLUDED IN SANITARY SEWER 8")	
205 15 LF SANITARY SEWER 6" (8"X6" WYE, ELBOW, CAP, AND ANY NECESSARY FITTINGS INCLUDED IN COST OF SANITARY SEWER 6") STA. 107+82.56 OFFSET 23.15 RT (CAP)	

SANITARY SEWER TAGS CONT.	
206 15 LF SANITARY SEWER 6" (8"X6" WYE, ELBOW, CAP, AND ANY NECESSARY FITTINGS INCLUDED IN COST OF SANITARY SEWER 6") STA. 107+97.51 OFFSET 22.49 RT (CAP)	
207 15 LF SANITARY SEWER 6" (8"X6" WYE, ELBOW, CAP, AND ANY NECESSARY FITTINGS INCLUDED IN COST OF SANITARY SEWER 6") STA. 108+23.97 OFFSET 22.13 (CAP)	

SANITARY SEWER TAGS CONT.	
208 15 LF SANITARY SEWER 6" (12"X6" WYE, ELBOW, CAP, AND ANY NECESSARY FITTINGS INCLUDED IN COST OF SANITARY SEWER 6") STA. 108+38.76 OFFSET 21.62 (CAP)	

COMPANY NAME: HRGreen
 PROJECT CONTACT: Michael G. Harding
 CLIENT: City of Aurora
 DATE PLOTTED: 7/26/2011 10:54:54 AM
 FILE NAME: 86090472-utl1-pnp01.dgn
 PLOT SCALE: 1"=20'
 PEN TABLE: 22x34.tbl

644.73	644.73	643.41	643.41	641.94	641.94	640.47	640.47	639.98	639.82	639.40	639.28	638.79	638.75	638.25	638.22	637.50	637.50	637.02	637.03	636.64	636.64	636.29	636.29	636.02	636.03
107+00	107+50	108+00	108+50	109+00	109+50	110+00	110+50	111+00	111+50	112+00	112+50	113+00													

	USER NAME = whood FILE NAME = 86090472-utl1-pnp01.dgn PLOT SCALE = 1"=20' PLOT DATE = 7/26/2011	DESIGNED - JPG DRAWN - WJH CHECKED - MGH DATE - 7/26/11	REVISED - REVISED - REVISED - REVISED -	CITY OF AURORA	UTILITY PLAN AND PROFILE DOWNER PLACE			F.A.U. RTE.	SECTION 07-00264-00-BR	COUNTY KANE	TOTAL SHEETS 164	SHEET NO. 24	CONTRACT NO. 63620
	SCALE: 1"=20'				SHEET NO. 1 OF 2 SHEETS	STA. 107+00 TO STA. 113+00	FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT						