



TURN ARROW, WHITE
15.6 SQ. FT. (TYP)

6" LANE LINE, WHITE
102 LIN. FT.

LETTERS, WHITE
20.8 SQ. FT. (TYP)

24" STOP BAR, WHITE

12" SOLID GORE
LINE, WHITE (TYP)

6" SOLID CROSSWALK
LINE, WHITE (TYP)

4" SKIP DASH, WHITE
10' DASH - 30' SKIP (TYP)
70 LIN. FT.

4" SKIP DASH, WHITE
10' DASH - 30' SKIP (TYP)

NOTES:

1. ALL EXISTING PAVEMENT MARKINGS REMOVED DURING CONSTRUCTION SHALL BE REPLACED ACCORDING TO THE PAVEMENT MARKING PLAN OR AS DIRECTED BY THE ENGINEER.
2. ALL EXISTING SIGNS REMOVED OR COVERED DURING CONSTRUCTION SHALL BE RESTORED IN THEIR ORIGINAL LOCATION PRIOR TO CONSTRUCTION OR AS DIRECTED BY THE ENGINEER.
3. NEW PAVEMENT MARKINGS SHALL BE PREFORMED PLASTIC PAVEMENT MARKING, TYPE C ON PORTLAND CEMENT CONCRETE PAVEMENT.
4. NEW PAVEMENT MARKINGS SHALL BE THERMOPLASTIC PAVEMENT MARKING ON HMA PAVEMENT.
5. SEE DISTRICT ONE TYPICAL PAVEMENT MARKINGS DETAIL FOR ADDITIONAL INFORMATION.

COMPANY NAME: HRGreen
 PROJECT CONTACT: Michael G. Harding
 CLIENT: City of Aurora
 DATE PLOTTED: 7/26/2011 10:57:44 AM
 FILE NAME: 86890472-pm_04_benton.dgn
 PLOT DRIVER: pdt101
 PEN TABLE: STRUC1 22x34.tbl



| | | |
|---------------------------------------|----------------|-----------|
| USER NAME = whood | DESIGNED - JMR | REVISED - |
| FILE NAME = 86890472-pm_04_benton.dgn | DRAWN - JMR | REVISED - |
| PLOT SCALE = | CHECKED - APS | REVISED - |
| PLOT DATE = 7/26/2011 | DATE - 7/26/11 | REVISED - |

CITY OF AURORA

**PAVEMENT MARKING PLAN
BENTON STREET**

SCALE: SHEET NO. 1 OF 3 SHEETS STA. TO STA.

| | | | | |
|---|----------------|--------|--------------|-----------|
| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| | 07-00264-00-BR | KANE | 164 | 43 |
| CONTRACT NO. 63620 | | | | |
| FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT | | | | |