



BILL OF MATERIALS

Bar No.	Size	Length	Shape
d502(E)	#5	2'- 8"	—
d503(E)	#5	3'- 5"	—
d504(E)	#5	2'- 9"	—
d505(E)	#5	1'- 9"	—
d506(E)	#5	1'- 6"	—
e501(E)	#4	27'- 10"	—
e502(E)	#4	16'- 0"	—
e503(E)	#4	13'- 10"	—
e504(E)	#4	19'- 6"	—
e505(E)	#4	20'- 4"	—
e506(E)	#4	5'- 6"	—
e507(E)	#4	22'- 0"	—
e508(E)	#4	21'- 2"	—
e509(E)	#4	14'- 6"	—
e510(E)	#4	16'- 2"	—
e511(E)	#4	9'- 5"	—
e512(E)	#4	13'- 7"	—
e513(E)	#4	7'- 9"	—
e514(E)	#4	6'- 9"	—
e515(E)	#4	10'- 3"	—
e516(E)	#4	11'- 1"	—
e517(E)	#4	6'- 11"	—
e518(E)	#5	7'- 9"	—
e519(E)	#4	12'- 10"	—
e520(E)	#4	14'- 0"	—
e521(E)	#4	15'- 6"	—
e522(E)	#4	17'- 8"	—
e523(E)	#4	8'- 9"	—
e524(E)	#4	7'- 8"	—
e525(E)	#4	3'- 0"	—
e526(E)	#4	1'- 2"	—
e527(E)	#4	8'- 10"	—
Reinforcement Bars, Epoxy Coated			Pound 2,678
Concrete Bridge Railing			Ft. 367
Pedestrian Rail (Special)			Ft. 3

Reinforcement bars given for information only. Included in cost for Concrete Bridge Railing (Special).
 * Epoxy Grout d506(E) bars according to Section 584 of the Standard Specifications.

COMPANY NAME: HRGreen
 CONTACT: HRGreen
 CLIENT: HRGreen
 DATE PLOTTED: 7/26/2011 11:04:50 AM
 FILE NAME: 86090412-E-Rail04.dgn
 PLOT DRIVER: pdfplot
 PEN TABLE: Struct 22x34.tbl

HRGreen.com
 Illinois Professional Design Firm
 #184-001322

USER NAME = whoold	DESIGNED - JPG	REVISED -
PLOT SCALE = N.T.S.	CHECKED - RGD	REVISED -
PLOT DATE = 7/26/2011	DRAWN - WJH	REVISED -
	CHECKED -	REVISED -

CITY OF AURORA
DOWNER PLACE OVER THE EAST BRANCH OF THE FOX RIVER

CONCRETE RAILING DETAILS
STRUCTURE NO. 045-6005
 SHEET NO. SE-15 OF SE-45 SHEETS

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	07-00264-00-BR	KANE	164	115
CONTRACT NO. 63620				
ILLINOIS FED. AID PROJECT				