

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	I-57 RURAL 90% FED 10% STATE 0004	I-57 RURAL 90% FED 10% STATE 0021	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	1685		1685
20400800	FURNISHED EXCAVATION	CU YD	5855		5855
25000210	SEEDING, CLASS 2A	ACRE	8.00		8.00
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	720		720
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	720		720
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	720		720
25100115	MULCH, METHOD 2	ACRE	8.00		8.00
25100630	EROSION CONTROL BLANKET	SO YD	408		408
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	780		780
28000500	INLET AND PIPE PROTECTION	EACH	11		11
28100107	STONE RIPRAP, CLASS A4	SO YD	103		103
28100201	STONE RIPRAP, CLASS A1	TON	7		7
28200200	FILTER FABRIC	SO YD	103		103
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SO YD	5507		5507
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SO YD	32		32
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	41613		41613
40600300	AGGREGATE (PRIME COAT)	TON	292		292
40600895	CONSTRUCTING TEST STRIP	EACH	4		4
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	3768		3768
40600990	TEMPORARY RAMP	SO YD	1222		1222
40603820	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N105	TON	10652		10652
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	10690		10690
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	25		25
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	85		85
44000100	PAVEMENT REMOVAL	SO YD	5508		5508
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	14708		14708
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	12582		12582
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	3531		3531
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SO YD	705		705
44000170	HOT-MIX ASPHALT SURFACE REMOVAL, 5 1/4"	SO YD	71304		71304
44200565	CLASS A PATCHES, TYPE II, 11 INCH	SO YD	101		101
44200569	CLASS A PATCHES, TYPE III, 11 INCH	SO YD	101		101
44200994	CLASS B PATCHES, TYPE II, 12 INCH	SO YD	30		30
44200998	CLASS B PATCHES, TYPE III, 12 INCH	SO YD	30		30
44201298	DOWEL BARS 1 1/4"	EACH	335		335
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	107		107
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	107		107
44213000	PATCHING REINFORCEMENT	SO YD	416		416
44213100	PAVEMENT FABRIC	SO YD	30		30
44213200	SAW CUTS	FOOT	2386		2386
44213208	TIE BARS 1 1/4"	EACH	264		264
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5554		5554
48203100	HOT-MIX ASPHALT SHOULDERS	TON	17015		17015

* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = keysrb	DESIGNED -	REVISED -
c:\pwwork\p\dot\keysrb\d0268570\057023-shit-500.dgn		DRAWN -	REVISED -
	PLOT SCALE = 40.000' / 1"	CHECKED -	REVISED -
	PLOT DATE = 6/14/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 1 OF 3 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34, 10-35)RS-2(SB)	CHAMPAIGN	66	4
FED. ROAD DIST. NO.			CONTRACT NO. 70923	
[ILLINOIS] FED. AID PROJECT				