

LOCATION	PREFORMED PAVEMENT MARKING SKIP-DASH WHITE 4"	THERMOPLASTIC PAVEMENT MARKING							AERIAL SPEED CHECK MARKING	SHORT TERM PAVEMENT MARKING	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKERS			WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING LINE 4"	PAVEMENT MARKING REMOVAL
		SKIP-DASH YELLOW 4"	SOLID WHITE 4"	SOLID YELLOW 4"	SOLID WHITE 6"	SOLID WHITE 8"	SOLID WHITE 12"	SOLID WHITE 24"				ONE WAY CRYSTAL	ONE WAY AMBER	TWO WAY AMBER			
STATION TO STATION	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH			
EAI 57 SOUTHBOUND																	
634+80.00 TO 764+96.99	3260			13017						3208	325	325			4479	13017	
765+00.00 TO 921+132.00	3900			15612						3988	390	390			5383	15612	
640+75.00 TO 643+22.00						247					7	7					556
643+22.00 TO 659+91.00			1669														
659+91.00 TO 663+00.00						309					9	9					
666+04.00 TO 749+03.00			8299														2766
690+80.00									12								
697+40.00									12								
704+00.00									12								
756+17.00 TO 759+03.00						286					8	8					
759+03.00 TO 764+96.99			594														198
765+00.00 TO 774+80.00			980														327
774+80.00 TO 778+43.00						363					10	10					
781+00.00 TO 921+12.00			14012														4671
798+00.00									12								
804+60.00									12								
811+20.00									12								
901+80.00									12								
908+40.00									12								
915+00.00									12								
SUB-TOTAL	7160	0	25554	28629	0	1205	0	0	108	7196	749	749	0	0	9862	28629	8518
OLYMPIAN RAMPS																	
RAMP A LT																	
10+88.00 TO 15+40.00				452						36					6		
15+40.00 TO 15+67.50				28						4					1		
RAMP A RT																	
11+02.00 TO 15+67.50			466							40					7		
RAMP B LT																	
13+11.50 TO 13+39.00				28							1	1					
13+39.00 TO 24+17.00				1078						2	13	13			1		
22+73.00 TO 24+30.00			157							84					13		
24+30.00 TO 24+90.00					203		121	36		2					1		
RAMP B RT																	
13+11.50 TO 24+31.00			1120							96					16		
RAMP C LT																	
13+70.00 TO 26+77.00			1307							112					18		
RAMP C RT																	
19+19.00 TO 21+63.00						244				18	6	6			3		
21+63.00 TO 22+13.00				50						4					1		
22+13.00 TO 26+97.00			484							42					7		
RAMP D LT																	
11+10.00 TO 28+17.00			1707							144	32	32			24		
RAMP D RT																	
11+08.00 TO 21+55.00				1047						84	11		11		1		
21+55.00 TO 22+05.00				50						4	2		2		4		
22+05.00 TO 25+13.00						308				24	8	8					
10+40.00 TO 10+86.00					158		95	36									
10+86.00 TO 12+92.00			206														
SUB-TOTAL	0	0	4963	3217	361	552	216	72	0	696	73	46	27	0	117	0	0

FILE NAME =	USER NAME = #USER*	DESIGNED -	REVISED -
#FILE#		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

PAVEMENT MARKING SCHEDULE

SCALE: SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	(10-34, 10-35)RS-2(SB)	CHAMPAIGN	66	20
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 70923	